

63 Fuller Way Berlin, CT 06037 860-953-8888 CT S1-390692 / CT SM1-2010 AA/EOE CT SBE

Ledyard Senior Center Ledyard, CT 06339 60 Kings Highway Gales Ferry, CT06335 Att: Shawn Ruszczyk

The following is a scope of work to be fully installed. Please feel free to call us with any questions and thank you for the opportunity to work with you on this project. Pricing is valid for 30 days from

Scope of work:

- Demo and dispose of 3 existing AHU's along with associated condensers
- Furnish and install (1) 2 ½ ton AHU-1 and adapt to existing ductwork
- Furnish and install (1) 2 ton AHU-2 and adapt to existing ductwork
- Furnish and install (1) 4 ton condenser on stand on pad to supply AHU 1 & 2
- Furnish and install (1) 4 ton AHU-3 and adapt to existing ductwork
- Furnish and install (1) 4 ton condenser on stand on pad to supply AHU-3
- Furnish and install refrigeration piping between all condensers and AHU's
- Furnish and install condensate drain piping for all equipment
- Furnish and install ductwork transitions for all equipment
- Furnish and install thermostats
- Furnish and install control wiring for all equipment
- Provide startup and commissioning
- Permit.
- Labor to complete work.

Total Amount	\$72,000.00 (Tax if Applicable)			
	bove is assumed to be excluded, Asbestos removal, painting, tax, and drop ceiling removal/replacement, fire alarms, saw ades, plaster wall or ceiling repair.			
Thank You, Jay Daigle VRF Division Manager				
XCustomer Name	X Air Temp Mechanical Services, Inc Contractor Name			
X	X <u>Jason Daigle</u> Jay Daigle, VRF Division Manager			