



GENERAL NOTES

1. MAP REFERENCES:
 - A) MAP OF LAND IN LEDYARD, CONN. PROPOSED FOR ACQUISITION BY THE BOROUGH OF GROTON, (DEPARTMENT OF UTILITIES) FOR WATER SUPPLY PURPOSES FOR L. F. DUTTON, SUPT.-DEPARTMENT OF UTILITIES AND METCALF AND EDDY, ENGINEERS, SCALE 1"=200' NOVEMBER 18, 1958. SCHOFIELD BROTHERS REGISTERED LAND SURVEYORS 48 PARK STREET FRAMINGHAM, MASSACHUSETTS, OFFICES IN FRAMINGHAM & ORLEANS, MASSACHUSETTS. REVISIONS: 1st.-FEB. 24, 1960 2nd.-MAR. 19, 1960 3rd.-MAY 2, 1960.
 - B) LOCATION OF RIGHT OF WAY OF THE CONNECTICUT LIGHT & POWER COMPANY ACROSS THE PROPERTY OF ELIZABETH M. CODERRE ET AL TOWN OF LEDYARD ; COUNTY OF NEW LONDON : STATE OF CONNECTICUT SCALE 1"=200' MAY 1965.
 - C) PLAN SHOWING TRACT OF LAND & BUILDINGS TO BE CONVEYED BY THE C. B. GRAVES, ESTATE W. NORBERT HILL, TRUSTEE TO THE TOWN OF LEDYARD LEDYARD, CONNECTICUT SCALE 1"=100' JANUARY 1987.
 - D) WICKSONS CONSERVATION SUBDIVISION EXISTING CONDITIONS PLAN PREPARED FOR GEBCO CONTRACTING, LLC 800 LONG COVE ROAD MAP 109 BLOCK 1340 LOT 800 LEDYARD, CONNECTICUT SCALE: 1"=100' JANUARY 18, 2007 SHEET C-3 CHERENZIA & ASSOCIATES, LTD.
 - E) RESUBDIVISION PLAN OVERALL COMPILATION PLAN PREPARED FOR DOROTHY SANTIN ATKINSON, TRUSTEE OF THE DOROTHY SANTIN ATKINSON REVOCABLE TRUST 770 LONG COVE ROAD LEDYARD, CONNECTICUT SCALE: 1"=50' SEPTEMBER 2011 JOB I.D. NO. 10-1943 SHEET 1 OF 4 REV "A" PER PLANNING COMMISSION APPROVAL 11-16-11.
 - F) WICKSONS CONSERVATION SUBDIVISION EXISTING CONDITIONS PLAN & LOT LAYOUT PLAN PREPARED FOR GEBCO CONTRACTING, LLC, 800 LONG COVE ROAD MAP 109, BLOCK 1340, LOT 800 LEDYARD, CONNECTICUT SCALE: 1"=100' DECEMBER 5, 2014.
2. THIS SUBDIVISION WILL BE SERVED BY ON-SITE WELLS AND ON SITE SEWAGE DISPOSAL SYSTEMS.
3. HOUSES, DRIVEWAYS, WELLS, SEWAGE DISPOSAL SYSTEMS, FOUNDATION DRAINS AND EROSION & SEDIMENT CONTROL ARE SHOWN CONCEPTUALLY.
4. ELEVATIONS SHOWN HEREON ARE BASED ON NATIONAL GEODETIC VERTICAL DATUM.
5. LOTS WITH SHARED DRIVES SHALL CONTAIN EASEMENTS FOR INGRESS AND EGRESS, THE RIGHT TO INSTALL AND MAINTAIN UTILITIES AND DRIVEWAY AND A MAINTENANCE AGREEMENT FOR THE SHARED DRIVEWAY.

GENERAL NOTES CONTINUED:

6. BULK REQUIREMENTS FOR EAGLES LANDING OPEN SPACE SUBDIVISION

ITEM	REQUIRED	PROVIDED
MINIMUM PARCEL AREA PRIOR TO SUBDIVISION	40 ACRES	169.65 ACRES
MINIMUM SIDE YARD DISTANCE	10 FEET (WITHIN EACH LOT)	10 FEET
MINIMUM BOTH SIDE YARDS (COMBINED)	25 FEET (WITHIN EACH LOT)	25 FEET
MINIMUM LOT REAR YARD DISTANCE	30 FEET (WITHIN EACH LOT)	30 FEET
MINIMUM FRONT YARD SETBACK	55 FEET FROM CENTERLINE OF ROAD OR 30 FEET FROM THE FRONT LOT LINE, WHICHEVER IS GREATER.	PROVIDED
MAXIMUM BUILDING HEIGHT	35 FEET	35 FEET
MAXIMUM IMPERVIOUS LOT COVERAGE	50%	LESS THAN 50%
MINIMUM LOT AREA	12,000 SQ. FT.	12,000 SQ. FT.
ROAD FRONTAGE	NOT APPLICABLE	
7. SOILS TESTING INDICATED ON THIS PLAN ARE REPRESENTATIVE OF ACTUAL SOIL CONDITIONS AND ADDITIONAL DEEP TEST PITS AND PERCOLATION TESTS MAY BE REQUIRED BY THE HEALTH DISTRICT IF THE BUILDING OR SYSTEM LOCATION IS ALTERED AND/OR THE SUITABLE SEPTIC AREA IS LIMITED.
8. UTILITIES TO BE INSTALLED UNDERGROUND.
9. MONUMENTS, PERMANENT PIN MARKERS OR BRASS PINS SHALL BE INSTALLED AT ALL CORNERS AND AT INTERVALS NO GREATER THAN 100 FEET ALONG THE BOUNDARIES OF ALL OPEN SPACE PARCELS. RIGHTS OF WAY TO OPEN SPACE PARCELS WHICH ARE 50 FEET IN WIDTH OR LESS SHALL BE MARKED AT INTERVALS NO GREATER THAN 50 FEET.
10. CALL BEFORE YOU DIG (1-800-922-4455) WILL BE CONTACTED PRIOR TO INITIATION OF THIS PROJECT.
11. WORK SHALL CONFORM TO ORDINANCE REGULATING THE ADDITION OF A NEW STREET OR HIGHWAY TO THE HIGHWAY SYSTEM OF THE TOWN OF LEDYARD.
12. ACTUAL CONDITIONS THAT DEVELOP OR ARE MORE CLEARLY ASSESSED DURING CONSTRUCTION MAY DICTATE THAT FIELD ADJUSTMENTS TO ACCOMMODATE DEVELOPMENT ACTIVITY, INCLUDING ADDITIONAL DRAINAGE OR SIGHTLINE CLEARING MEASURES, MAY BE NECESSARY. ADDITIONAL DESIGN EFFORT FOR AND INSTALLATION OF SUCH MEASURES SHALL BE UNDERTAKEN IN CONSULTATION WITH AND AT NO EXPENSE TO THE TOWN.
13. ON JUNE 5, 2018 THE LEDYARD INLAND WETLANDS AND WATERCOURSES COMMISSION REVIEWED THIS SUBDIVISION. APPLICATION IW 18-2 79 VINEGAR HILL ROAD SUBDIVISION OF 170.16 ACRES INTO 25 BUILDING LOTS. THIS PROPOSAL WAS CLASSIFIED "B" NOT SIGNIFICANT IMPACT TO THE WETLANDS. THE COMMISSION APPROVED THIS APPLICATION WITH STIPULATIONS AS FOLLOWS:
 1. REVIEW OF PROPOSED PROJECT DRAINAGE BY STAFF AND TOWN ENGINEER RECOMMENDED.
 2. OVERSIGHT OF PROJECT CONSTRUCTION BY THE WETLANDS ENFORCEMENT OFFICER.
 3. SUBMISSION OF CROSS-SECTION DETAIL OF DRIVEWAY CROSSING FOR THE SHARED DRIVEWAY ACCESSING LOTS 13 & 15.
 4. PLACEMENT OF INLAND WETLANDS AND WATERCOURSES COMMISSION PLACARDS AT CORNERS ADJACENT TO WETLANDS ON 17 THROUGH 23 AND 15 AND 25 MARTY'S WAY.
14. THE TOWN OF LEDYARD SHALL SUPPLY AND INSTALL STREET SIGNAGE AND MARKINGS SPECIFIED BY THESE PLANS AT THE EXPENSE OF DEVELOPER. UPON COMPLETION OF WORK THE TOWN WILL PRESENT AN INVOICE TO THE DEVELOPER FOR THE MATERIALS AND LABOR ASSOCIATED WITH THIS EFFORT.
15. SECTION 4.6 OF THE SUBDIVISION REGULATIONS WAS FOLLOWED IN THE DESIGN OF THIS SUBDIVISION.
16. IN THE EVENT THAT ANY BLASTING IS REQUIRED, THE BLASTER WILL CONDUCT A PRE-BLAST SURVEY.
17. THE APPLICANT SHALL CONSTRUCT SHARED DRIVEWAYS PRIOR TO THE SALE OF THEIR RESPECTIVE LOTS.
18. PORTIONS OF THIS RE-SUBDIVISION ARE SERVICED BY COMMON DRIVEWAYS. THE TOWN OF LEDYARD WILL PROVIDE NO MAINTENANCE, REPAIRS OR SCHOOL BUS SERVICE ALONG COMMON DRIVEWAY.




SOILS LEGEND

Aa	- ADRIAN AND PALMS MUCKS
CdC	- CANTON AND CHARLTON EXTREMELY STONY FINE SANDY LOAMS, 3 TO 15 PERCENT SLOPES
CcB	- CANTON AND CHARLTON VERY STONY FINE SANDY LOAMS, 3 TO 8 PERCENT SLOPES
CcC	- CANTON AND CHARLTON VERY STONY FINE SANDY LOAMS, 8 TO 15 PERCENT SLOPES
CrC	- CHARLTON-HOLLIS FINE SANDY LOAMS, 3 TO 15 PERCENT SLOPES
CrD	- CHARLTON-HOLLIS FINE SANDY LOAMS, VERY ROCKY, 15 TO 45 PERCENT SLOPES
CdC	- CANTON AND CHARLTON EXTREMELY STONY FINE SANDY LOAMS, 3 TO 15 PERCENT SLOPES
CdD	- CANTON AND CHARLTON EXTREMELY STONY FINE SANDY LOAMS, 15 TO 35 PERCENT SLOPES
CrD	- CHARLTON-HOLLIS FINE SANDY LOAMS, VERY ROCKY, 15 TO 45 PERCENT SLOPES
HrC	- HOLLIS-CHARLTON-ROCK OUTCROP COMPLEX, 3 TO 15 PERCENT SLOPES
HrD	- HOLLIS-CHARLTON-ROCK OUTCROP COMPLEX, 15 TO 45 PERCENT SLOPES
Rn	- RIDGEBURY, LEICESTER, AND WHITMAN EXTREMELY STONY FINE SANDY LOAMS
SxB	- SUTTON EXTREMELY STONY FINE SANDY LOAM, 0 TO 8 PERCENT SLOPES

TOTAL AREA = 169.65 ACRES
 OPEN SPACE PROVIDED = 102.25 ACRES (OPEN SPACE LEFT IN ITS NATURAL STATE (60.1%))
 OPEN SPACE REQUIRED = 102.10 ACRES (60% OF SITE)

SHEET INDEX

SHEET -1	200 SCALE MAP, GENERAL NOTES LOCATION MAP
SHEET -2	200 SCALE PLAN PARCEL HISTORY MAP
SHEET -3	40 SCALE A-2 PLAN
SHEET -4	40 SCALE A-2 PLAN
SHEET -5	40 SCALE A-2 PLAN
SHEET -6	40 SCALE A-2 PLAN
SHEET -7	40 SCALE CONCEPTUAL LAYOUT
SHEET -8	40 SCALE CONCEPTUAL LAYOUT
SHEET -9	40 SCALE CONCEPTUAL LAYOUT
SHEET -10	40 SCALE CONCEPTUAL LAYOUT
SHEET -11	40 SCALE PLAN/PROFILE MARTY'S WAY
SHEET -12	DEEP TEST PIT DATA/PERCOLATION TEST DATA
SHEET -13	DEEP TEST PIT DATA/SEPTIC SYSTEM DESIGN CRITERIA
SHEET -14	CONSTRUCTION DETAILS
SHEET -15	CONSTRUCTION SEQUENCING AND EROSION AND SEDIMENT CONTROL NARRATIVE/DETAILS
SHEET -15A	A-2 SURVEY 13, 15, 24, 25, 26, 27 AND 28 MARTY'S WAY



DIETER & GARDNER
 LAND SURVEYORS • PLANNERS
 P.O. BOX 335
 1641 CONNECTICUT ROUTE 12
 GALES FERRY, CT. 06335
 (860) 464-7455
 EMAIL: DIETER.GARDNER@YAHOO.COM

LEGEND

	STONE WALL
	PROPERTY LINE
	STREET LINE
	UTILITY POLE
	STREET ADDRESS
	SOIL TYPE PER SOILS SURVEY OF NEW LONDON COUNTY

NOTE: BOUNDARY LINES OF ADJOINING PROPERTIES ARE SHOWN FOR GENERAL INFORMATIONAL PURPOSES ONLY AND ARE NOT TO BE CONSTRUED AS BEING ACCURATELY LOCATED OR DEPICTED.
 THE STONE WALLS AND/OR FENCES SHOWN AS BOUNDARIES MAY HAVE IRREGULARITIES OF COURSE BETWEEN PRINCIPAL POINTS OF COURSE INDICATED.

THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB# 17-047.DWG FBK#300

THE WORD "CERTIFY" IS UNDERSTOOD TO BE AN EXPRESSION OF THE PROFESSIONAL OPINION BY THE LAND SURVEYOR WHICH IS BASED ON HIS OR HER BEST KNOWLEDGE, INFORMATION AND BELIEF, AS SUCH IT CONSTITUTES NEITHER GUARANTEE OR WARRANTY.

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____

CHAIRMAN OR SECRETARY _____ DATE _____

LOT NUMBERS ASSIGNED BY THE ASSESSOR

ASSESSOR _____ DATE _____

IWWC APPLICATION# _____

APPROVED, _____

NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)

NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA; NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)

ZONING/WETLANDS OFFICER _____ DATE _____

APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.

PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION

CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

PLAN SHOWING EAGLES LANDING AN OPEN SPACE SUBDIVISION PROPERTY OF MR G 1 LLC 79 VINEGAR HILL ROAD LEDYARD, CONNECTICUT SCALES AS SHOWN JUNE 2022

I CERTIFY THAT THIS SURVEY AND MAP HAS BEEN PREPARED IN ACCORDANCE WITH SECTIONS 20-300b-1 THRU 20-300b-20 OF THE REGULATIONS OF CONNECTICUT STATE AGENCIES - "MINIMUM STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT" AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC. IT IS A BOUNDARY SURVEY CONFORMING TO HORIZONTAL ACCURACY CLASS "D" TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

TITLE: LAND SURVEYOR CT No. 14208
 DATE: JUNE 3, 2022