

# GOLIATH

**STRUCTURAL STEEL MAINTENANCE LLC.**

258 MEADOW STREET  
CARVER, MA. 02330

774-454-3369

68 BRIGHTON ROAD  
CROYDON, NH. 03773

## PROPOSAL

GROTON UTILITIES

10/10/2022

295 MERIDAN STREET

GROTON, CT. 06340

ATTN: MOE DUARTE

### ROOF CLEANING AND RECOATING:

**ALL ROOF SURFACES WILL RECEIVE A FULL POWERWASH (5000PSI/ROTARY ZERO NOZZLE) TO REMOVE ALL FAILED COATINGS, SALT, AND OTHER DEBRIS.**

**ALL ROOF SURFACES WILL THEN BE MACHANICALLY ABRADED TO INSURE PROPER PROFILE AND ADHESION OF NEW PAINT.**

**PRIME COAT WILL BE PPG'S AMERLOCK 2-400 EPOXY (5-8 MILS D.F.T.)**

**FINISH COAT WILL BE PPG'S PSX 700 SILOXANE (4-6 MILS D.F.T.)**

**TOTAL = \$32,500.00**

# **ALTERNATIVE #1: FULL EXTERIOR RECOAT**

**TO EXECUTE THIS SCOPE OF WORK A RIGID CONTAINMENT WOULD NEED TO BE CONSTRUCTED THEN SHRINKWRAPED TO INCLUDE DUST AND ENVIRONMENTAL CONTROLS.**

**THE EXTERIOR COATINGS ARE IN VERY GOOD CONDITION BUT NEED TO BE ABRADED TO INSURE PROPER ADHESION OF NEW PAINT. THIS WILL BE DONE BY WET OR DRY BRUSH BLASTING OF ALL EXTERIOR SURFACES, SPECIAL ATTENTION WILL BE GIVEN TO DELAMINATED ROOF SURFACES TO INSURE ALL LOOSE COATINGS ARE REMOVED.**

**PRIME COAT WILL BE PPG'S AMERLOCK 2-400 (5-8 MILS D.F.T.)**

**FINISH COAT WILL BE PPG'S PSX 700 SILOXANE (4-6 MILS D.F.T.)**

**TOTAL = \$285,000.00**

**THE PAINT SYSTEM FOR BOTH OF THESE BIDS IS DESIGNED TO EXTEND THE LIFE OF YOUR CURRENT PAINT SYSTEM, YOU CAN EXPECT TEN YEARS OR MORE OF CONTINUED SERVICE.**

**RESPECTFULLY,**

**JEFFREY A. REED**

**GOLIATH STRUCTURAL STEEL MAINTENANCE**

**THANK YOU!**