

P.O. Box 258
32 Exeter Road
Lebanon, Connecticut 06249



Phone: (860) 642-9952
Fax: (860) 642-9953
www.kroppenvironmental.com

September 8, 2025

KEC 09-25

Mr. Evan Smith
Gales Ferry Fire Department
1772 Route 12
Gales Ferry, CT 06335

Re: **Quotation for AFFF Foam System Decontamination and Disposal**
Gales Ferry Fire Department
1772 Route 12
Gales Ferry, CT 06335

Kropp Environmental Contractors, Inc. is pleased to provide this quotation for services at the above-referenced site in Gales Ferry, CT (the site).

Scope of Work I (Draining and Rinsing AFFF From Onboard Systems)

- A. Prepare and submit all transportation and waste profile paperwork as necessary
- B. Establish secondary containment utilizing poly sheeting and absorbent material to prevent secondary contamination of the surrounding area.
- C. Utilize appropriate PPE as required.
- D. Minimize the use of additional equipment and material for the drainage and rinsing process. All materials and equipment utilized that come to contact with the foam or rinse water will be disposed of as PFAS contaminated waste
- E. Drain all accessible AFFF foam from one (1) 30-gallon tank utilizing existing associated plumbing into DOT shippable containers as applicable. Containers will be stored as a separate waste stream and labelled as "Drained AFFF Concentrate."
- F. Separate containers of unused AFFF foam shall be drained into the above mentioned "Drained AFFF Concentrate" containers as applicable. Separate containers of unused AFFF foam in DOT shippable condition shall be labelled for shipping as required.
- G. Perform a hot water rinse of the tank system including plumbing, utilizing an environmentally friendly biodegradable detergent (Simple Green).
- H. Allow rinse water to stay in the tank system no less than 30 minutes before draining the rinse water through the existing associated plumbing into DOT shippable containers as applicable. Containers will be stored as a separate waste stream and labelled as "PFAS Foam Rinsate."
- I. Perform the rinse soak and drain process no fewer than three (3) times in succession.

Quotation for AFFF Foam System Decontamination and Disposal – KEC 09-25

Gales Ferry Fire Department

1772 Route 12, Gales Ferry, CT 06335

Page 2

- J. Store all PPE, equipment, and material utilized that has come into contact with AFFF foam or rinsewater during cleaning activities in DOT shippable containers as applicable. Containers will be stored as a separate waste stream and labelled as “PFAS Contaminated PPE and Misc Debris”, to include any drained containers mentioned above.
- K. Store containers on site in a protected area within secondary containment until delivery can be made to the disposal facility.
- L. Transport and dispose of AFFF foam, rinse water, and PPE to an approved disposal facility.

The cost for **Scope of Work I** is **Three Thousand Six Hundred Fifty Dollars (\$3,650.00) plus the cost of containers, facility profile fee, transportation, and disposal**, which shall be billed according to the following schedule:

- **New 55-Gallon Drum - \$110.00 per drum**
- **Transportation – \$680.00 per trip to the disposal facility**
- **Profile Fee: One Hundred Fifty Dollars per Profile (\$150.00/Profile)**
- **Disposal of PFAS Concentrate: Four Hundred Seventy-Seven Dollars per Drum (\$477.00/Drum)**
- **Disposal of PFAS Rinsate: Four Hundred Seventy-Seven Dollars per Drum (\$477.00/Drum)**
- **Disposal of PFAS PPE and Misc. Debris: Seven Hundred Seventy-Four Dollars per Drum (\$774.00/Drum)**

Drum disposal costs are based upon current market rates. Actual disposal will be billed at cost to KEC plus 15%.

This estimate is based on assumptions made on the nature and character of the waste at the time of writing. Final billing will be based on actual waste disposal.

<i>Summary of Costs</i>			
Scope of Work	Cost/Unit	Units Estimated	Total
SOW I- Draining and Rinsing	\$3,650.00/Event	1 Event	\$ 3,650.00
SOW I- New Drums	\$110.00/Drum	4 Drums	\$ 440.00
SOW I- Profile Fees	\$150.00/Profile	3 Profiles	\$ 450.00
SOW I- Transportation	\$680.00/Trip	1 Trip	\$ 680.00
SOW I- AFFF Disposal	\$477.00/Drum	1 Drum	\$ 477.00
SOW- Rinsate Disposal	\$477.00/Drum	2 Drums	\$ 954.00
SOW I- PPE Disposal	\$774.00/Drum	1 Drum	\$ 774.00
TOTAL			\$ 7,425.00

Payment is due upon job completion.

Quotation for AFFF Foam System Decontamination and Disposal – KEC 09-25

Gales Ferry Fire Department

1772 Route 12, Gales Ferry, CT 06335

Page 3

All work will be done in a workmanlike manner, in a reasonable length of time, and according to state and federal regulations.

A finance charge of 1 1/2% per month (18% Annual Percentage Rate) will be charged on all invoices 30 days past due. All accounts are subject to attorney and collection fees.

KEC is a Connecticut permitted Emergency Spill Clean-Up Contractor and licensed Hazardous Waste Hauler (CT-HW-690); a Rhode Island licensed Emergency Spill Clean-Up Contractor and licensed Hazardous Waste Hauler (RI-804); a New York licensed Hazardous Waste Hauler (CT-138); an Asbestos Abatement Contractor (CT-000302); and a Tank and Pump Contractor (P9-00279287). KEC also retains a Licensed Environmental Professional (LEP) on-staff.

Please feel free to contact me at 860-642-9952 with any questions.

Respectfully submitted,

A handwritten signature in blue ink that reads "Sally W. Kropp Pres.".

Sally W. Kropp
President

APPROVED: _____ **DATE:** _____