



63 Fuller Way
Berlin, CT 06037
860-953-8888
CT S1-390692 / CT SM1-2010
AA/EOE
CT SBE

Ledyard Senior Center
Ledyard, CT 06339
60 Kings Highway
Gales Ferry, CT06335

Att: Shawn Ruszczyk

The following is a scope of work to be fully installed. Please feel free to call us with any questions and thank you for the opportunity to work with you on this project. Pricing is valid for 30 days from

Scope of work:

- Demo and dispose of 3 existing AHU’s along with associated condensers
- Furnish and install (1) 2 ½ ton AHU-1 and adapt to existing ductwork
- Furnish and install (1) 2 ton AHU-2 and adapt to existing ductwork
- Furnish and install (1) 4 ton condenser on stand on pad to supply AHU 1 & 2
- Furnish and install (1) 4 ton AHU-3 and adapt to existing ductwork
- Furnish and install (1) 4 ton condenser on stand on pad to supply AHU-3
- Furnish and install refrigeration piping between all condensers and AHU’s
- Furnish and install condensate drain piping for all equipment
- Furnish and install ductwork transitions for all equipment
- Furnish and install thermostats
- Furnish and install control wiring for all equipment
- Provide startup and commissioning
- Permit.
- Labor to complete work.

Total Amount.....\$72,000.00 (Tax if Applicable)

Exclusions: Anything not specifically stated above is assumed to be excluded, Asbestos removal, painting, tax, 2nd shift, engineered drawings, line voltage, bonds, and drop ceiling removal/replacement, fire alarms, saw cutting, structural steel, electrical service upgrades, plaster wall or ceiling repair.

Thank You,
Jay Daigle
VRF Division Manager

X _____
Customer Name

X Air Temp Mechanical Services, Inc
Contractor Name

X _____
Customer Signature & Date

X Jason Daigle
Jay Daigle, VRF Division Manager

