


BOUNDARY AND SOILS MAP
THIS IS NOT A SURVEY
TOTAL AREA = 9.21 ACRES
GRAPHIC SCALE



APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____	
CHAIRMAN OR SECRETARY	DATE
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____	
LOT NUMBERS ASSIGNED BY THE ASSESSOR	
ASSESSOR	DATE
IWVC APPLICATION#	DATE
APPROVED,	
NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)	
NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA: NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)	
WETLANDS OFFICER	DATE
APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.	
PUBLIC WORKS DIRECTOR/TOWN ENGINEER	DATE
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION	
CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION	DATE
APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION	
ZONING ENFORCEMENT OFFICER	DATE

LEGEND


- STONE WALL
- - - PROPERTY LINE
- - - STREET LINE
- 98 STREET NUMBER

SOILS LEGEND

- Afb - AGAWAM FINE SANDY LOAM, 3 TO 8 PERCENT SLOPES
- CdC - CANTON AND CHARLTON EXTREMELY STONY FINE SANDY LOAMS, 3 TO 15 PERCENT SLOPES
- CrD - CHARLTON-HOLLIS FINE SANDY LOAMS, VERY ROCKY, 15 TO 45 PERCENT SLOPES
- HcA - HAVEN SILT LOAM, 0 TO 3 PERCENT SLOPES
- HkC - HINCKLEY GRAVELLY SANDY LOAM, 3 TO 15 PERCENT SLOPES
- Rn - RIDGEBURY, LEICESTER AND WHITMAN EXTREMELY STONY FINE SANDY LOAM
- Ud - UDORTENTS-URBAN LAND COMPLEX

THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB# 22-007.DWG FBK#327


NOTE: BOUNDARY LINES OF ADJOINING PROPERTIES ARE SHOWN FOR GENERAL INFORMATIONAL PURPOSES ONLY AND ARE NOT TO BE CONSTRUED AS BEING ACCURATELY LOCATED OR DEPICTED.



PARCEL HISTORY MAP
THIS IS NOT A SURVEY


PARCEL HISTORY
TOTAL AREA ON MARCH 22, 1962 = 9.21 ACRES
TOTAL NUMBER OF LOTS CREATED FROM ORIGINAL TRACT = 4

GRAPHIC SCALE




DIETER & GARDNER
LAND SURVEYORS • PLANNERS
P.O. BOX 335
1641 CONNECTICUT ROUTE 12
GALES FERRY, CT. 06335
(860) 464-7455
EMAIL: DIETER.GARDNER@YAHOO.COM

- GENERAL NOTES:
- MAP REFERENCES:
A) SUBDIVISION PLAN PREPARED FOR AMER JAVAD 98 STODDARDS WHARF ROAD - (CONN. RTE #214) LEDYARD, CONNECTICUT BOUNDARY SURVEY. MAP DATE: 9/12/11 SCALE: 1"=40' SHEET 1 OF 4 ADVANCED SURVEYS, LLC.
B) LOT DIVISION PLAN PROPERTY OF PANDE HOLDINGS, LLC 98 STODDARDS WHARF (CONNECTICUT ROUTE 214) LEDYARD, CONNECTICUT DATE: MAY 10, 2007 SCALE: 1"=40' SHEET NO. 1 OF 2. REVISIONS DATE 5/23/07 STREET ADDRESS, LOCATION MAP & NOTE 12 ADDED.
 - CALL BEFORE YOU DIG AT 1-800-922-4455 BEFORE ANY CONSTRUCTION ACTIVITY.
 - ELEVATIONS SHOWN HEREON ARE BASED ON NATIONAL GEODETIC VERTICAL DATUM.
 - THIS SUBDIVISION WILL BE SERVED BY ON SITE WELLS AND ON SITE SEWAGE SYSTEMS.
 - HOUSES, WELLS, DRIVEWAYS, SEWAGE DISPOSAL SYSTEMS AND EROSION/SEDIMENT CONTROL MEASURES ARE SHOWN CONCEPTUALLY ONLY.
 - ZONING SETBACKS: LOTS SUBMITTED AS A SET-ASIDE DEVELOPMENT AS DEFINED IN CONNECTICUT GENERAL STATUTES SECTION 8-30g.
MINIMUM FRONT YARD SETBACK 12'
MINIMUM SIDE YARD SETBACK 6'
MINIMUM REAR YARD SETBACK 15'
 - PASSIVE SOLAR TECHNIQUES AS PRESCRIBED BY LAW HAVE BEEN CONSIDERED IN THE DESIGN OF THIS SUBDIVISION.



LOCATION MAP
ZONING DISTRICT: R-60

GRAPHIC SCALE



SHEET INDEX

- SHEET 1 - 100 SCALE BOUNDARY MAP; PARCEL HISTORY MAP; LOCATION MAP AND GENERAL NOTES
- SHEET 2 - 40 SCALE A-2 PLAN
- SHEET 3 - 40 SCALE CONCEPTUAL LAYOUT PLAN
- SHEET 4 - DEEP TEST PIT DATA
- SHEET 5 - PERCOLATION TEST RESULTS AND SEPTIC SYSTEM DESIGN CRITERIA
- SHEET 6 - 40 SCALE PLAN/PROFILE AVERY BROOK CIRCLE
- SHEET 7 - 40 SCALE PLAN/PROFILE AVERY BROOK CIRCLE
- SHEET 8 - 40 SCALE SIGHTLINE DEMONSTRATION PLAN
- SHEET 9 - EROSION AND SEDIMENT CONTROL NARRATIVE AND DETAILS
- SHEET 10 - CONSTRUCTION DETAILS

PLAN SHOWING
RESUBDIVISION
PROPERTY OF
AVERY BROOK HOMES LLC
94, 96, 98 AND 100
STODDARDS WHARF ROAD
A.K.A.
CONNECTICUT ROUTE 214
LEDYARD, CONNECTICUT
SCALES AS SHOWN

JULY 2022
REVISED: OCTOBER 31, 2022

SHEET 1 OF 10

THIS SURVEY AND MAP HAS BEEN PREPARED IN ACCORDANCE WITH SECTIONS 20-300b-1 THRU 20-300b-20 OF THE REGULATIONS OF CONNECTICUT STATE AGENCIES - "MINIMUM STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT" AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC. IT IS A BOUNDARY SURVEY BASED ON AN RESURVEY CONFORMING TO HORIZONTAL ACCURACY CLASS "D". TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

TITLE: LAND SURVEYOR CT No. 14208
DATE: JULY 7, 2022

DEEP TEST PIT DATA

WITNESSED AND RECORDED BY WENDY BROWN-ARNOLD RS,REHS AND ALEX WILBOUR LEDGE LIGHT HEALTH DISTRICT ON 5/2/22, 5/5/22 AND 5/23/2022 AND WENDY BROWN-ARNOLD RS,REHS ON JUNE 14, 2022.

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____

CHAIRMAN OR SECRETARY _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____

LOT NUMBERS ASSIGNED BY THE ASSESSOR _____ DATE _____

ASSESSOR _____ DATE _____

ITWC APPLICATION# _____ APPROVED _____

NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)

NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA. NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)

WETLANDS OFFICER _____ DATE _____

APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT. _____ DATE _____

PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION _____ DATE _____

ZONING ENFORCEMENT OFFICER _____ DATE _____

TP 1
0-45" FILL-DISTURBED
LOAM, ROCKS, BRICK
NO MOTTLING
NO WATER
LEDGE @ 45"

TP 2
0-16" DISTURBED SOIL & FILL
16-50" LIGHT TAN FINE SAND
W/GRAVEL & ROCKS
NO MOTTLING
NO WATER
LEDGE @ 50"

TP 3
0-10" TOPSOIL
10-28" LIGHT BROWN FINE SANDY LOAM
28-87" LIGHT TAN FINE SAND W/GRAVEL
COBBLES, LARGE STONES
NO MOTTLING
NO WATER
NO LEDGE

TP 4
0-11" TOPSOIL
11-34" LIGHT BROWN FINE SANDY LOAM
34-90" LIGHT TAN/GRAY FINE SAND W/
GRAVEL, SOME COBBLES
MOTTLING @ 64"
WATER @ 80"
NO LEDGE

TP 5
0-16" TOPSOIL
16-45" LIGHT BROWN SILT LOAM, SOME FINE SAND
45-94" TAN/GRAY FINE TO MED. SAND W/
GRAVEL
MOTTLING @ 33"?
WATER @ 33"
NO LEDGE

TP 6
0-9" TOPSOIL
9-37" BROWN FINE TO VERY FINE SANDY LOAM
37-84" TAN/GRAY FINE TO MED. SAND W/
GRAVEL, FEW COBBLES
MOTTLING @ 46"
WATER @ 50"
NO LEDGE

TP 7
0-7" TOPSOIL
7-30" BROWN FINE TO MED. SANDY LOAM
30-77" TAN COARSE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 8
0-10" TOPSOIL
10-34" LIGHT BROWN FINE SANDY LOAM
34-64" ORANGE/TAN COARSE SAND
W/GRAVEL
64-95" TAN/GRAY FINE TO MED. SAND
MOTTLING @ 73"
WATER @ 83"
NO LEDGE

TP 9
0-15" TOPSOIL
15-31" BROWN FINE SANDY LOAM
31-96" TAN MED. TO COARSE SAND AND
GRAVEL, FEW COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 10
0-11" TOPSOIL
11-23" BROWN FINE SANDY LOAM
23-84" TAN TO GRAY MED. TO COARSE SAND W/
GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 11
0-11" TOPSOIL
11-34" BROWN FINE TO MED. SANDY LOAM
34-96" TAN TO GRAY MED. TO COARSE SAND W/
GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 12
0-12" TOPSOIL
12-29" BROWN FINE TO MED. SANDY LOAM
29-95" BROWN TO TAN MED. TO COARSE SAND W/
GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 13
0-13" TOPSOIL
13-26" BROWN FINE TO MED. SANDY LOAM
26-91" TAN TO GRAY MED. TO COARSE SAND AND
GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 14
0-8" TOPSOIL
8-26" BROWN FINE TO MED. SANDY LOAM
26-91" TAN MED. TO FINE SAND/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 15
0-10" TOPSOIL
10-39" BROWN FINE SANDY LOAM
39-99" TAN TO OLIVE MED. TO COARSE SAND/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 16
0-11" TOPSOIL
11-37" BROWN FINE TO MED. SANDY LOAM
37-96" TAN TO GRAY MED. TO FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 17
0-11" TOPSOIL
11-37" BROWN FINE TO MED. SANDY LOAM
37-89" TAN TO GRAY MED. TO FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 18
0-9" TOPSOIL
9-29" YELLOW TO BROWN FINE SANDY LOAM
29-103" TAN TO OLIVE MED. TO COARSE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 19
0-14" TOPSOIL
14-36" BROWN FINE SANDY LOAM
36-84" TAN/GRAY COARSE SAND
W/GRAVEL
MOTTLING @ 40"
WATER @ 45"
NO LEDGE

TP 20
0-17" TOPSOIL
17-31" BROWN FINE SANDY LOAM
31-83" TAN/GRAY COARSE SAND
W/GRAVEL AND FEW COBBLES
MOTTLING @ 43"
WATER @ 46"
NO LEDGE

TP 21
0-17" SANDY FILL & DISTURBED
17-24" TOPSOIL
24-33" BROWN MED. SANDY LOAM
33-88" TAN/BROWN FINE MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 22
0-19" FILL
19-32" TOPSOIL
32-53" BROWN MED. SANDY LOAM
53-103" TAN TO BROWN MED. TO FINE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 23
0-17" SANDY FILL AND DISTURBED
17-24" TOPSOIL
24-33" BROWN MED. SANDY LOAM
33-88" TAN TO BROWN MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 24
0-8" TOPSOIL
8-46" BROWN FINE TO MED. SANDY LOAM,
SOME COBBLES
46-92" TAN TO GRAY COARSE SAND
W/GRAVEL AND COBBLES
MOTTLING @ 60"
WATER 64" UPHILL, 32" DOWNHILL
NO LEDGE

TP 25
0-10" TOPSOIL
10-29" BROWN FINE TO MED. SANDY LOAM,
SOME SILT
29-75" BROWN TO GRAY MED. TO COARSE
SAND W/GRAVEL AND COBBLES
MOTTLING @ 33"
WATER 33", 30" DOWNHILL
NO LEDGE

TP 26
0-7" TOPSOIL
7-36" YELLOW TO BROWN FINE TO MED.
SILTY LOAM W/TRACE FINE SAND
36-82" BROWN TO GRAY FINE TO MED.
SAND W/GRAVEL AND COBBLES, SOME SILT
MOTTLING @ 26"
WATER @ 26"
NO LEDGE

TP 27
0-11" TOPSOIL
11-24" BROWN FINE TO MED. SANDY LOAM
24-39" TAN FINE TO MED. SAND
39-87" TAN TO GRAY MED. TO FINE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 28
0-12" TOPSOIL
12-32" LIGHT BROWN FINE TO MED. SANDY LOAM
32-96" LIGHT TAN FINE TO MED. SAND W/
GRAVEL AND COBBLES STRATIFIED
NO MOTTLING
NO WATER
NO LEDGE

TP 29
0-12" TOPSOIL
12-32" BROWN FINE TO MED. SANDY LOAM
32-99" TAN TO GRAY MED. TO FINE SAND W/
GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 30
0-12" TOPSOIL
12-34" BROWN FINE SANDY LOAM (DEPTH VARIES)
34-98" TAN TO MED. TO FINE SAND W/GRAVEL AND
GRAVEL, STRATIFIED
NO MOTTLING
NO WATER
NO LEDGE

TP 31
0-7" TOPSOIL
7-31" YELLOW TO BROWN FINE TO VERY FINE SANDY LOAM
31-100" TAN FINE TO MED. SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 32
0-8" TOPSOIL
8-34" BROWN FINE SANDY LOAM
34-82" TAN TO GRAY MED. TO FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 33
0-10" TOPSOIL
10-34" BROWN FINE SANDY LOAM
34-75" TAN TO GRAY MED. TO FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 34
0-12" TOPSOIL
12-44" YELLOW TO BROWN FINE TO VERY FINE SANDY LOAM
44-89" TAN TO BROWN MED. SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 35
0-9" TOPSOIL
9-21" BROWN FINE SANDY LOAM
21-47" TAN TO BROWN MED. SAND W/GRAVEL,
FEW COBBLES
47-110" TAN TO BROWN, MED. SAND W/GRAVEL,
FEW COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 36
0-8" TOPSOIL
8-34" BROWN FINE SANDY LOAM
34-94" TAN TO GRAY MED. TO
FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 37
0-9" TOPSOIL
9-39" LIGHT BROWN TO TAN,
FINE TO VERY FINE, SANDY LOAM
39-100" LIGHT TAN FINE TO MED.
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 38
0-8" TOPSOIL
8-34" BROWN FINE SANDY LOAM
34-90" TAN TO GRAY MED. TO FINE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 39
0-5" TOPSOIL
5-41" LIGHT BROWN FINE SANDY LOAM
41-83" TAN TO MED. SAND W/
GRAVEL AND COBBLES
83"-104" OLIVE TO BROWN FINE SAND,SOME GRAVEL
NO MOTTLING
NO WATER
NO LEDGE

TP 40
0-8" TOPSOIL
8-32" BROWN FINE TO MED. SANDY LOAM
32-58" TAN TO GRAY SILT WITH
PATCHY ORANGE REDOX INCONSISTENT AROUND
58-99" TAN TO GRAY MED. TO FINE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 41
0-9" TOPSOIL
9-29" BROWN FINE TO MED. SANDY LOAM
29-52" TAN TO GRAY SILT
52-101" TAN TO GRAY, FINE TO MED. SAND
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 42
0-5" TOPSOIL
5-14" LIGHT BROWN FINE TO VERY FINE SANDY LOAM
14-50" ORANGE TO GRAY SILT, STAINED
50-105" TAN TO BROWN FINE TO MED.
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 43
0-8" TOPSOIL
8-33" BROWN FINE SANDY LOAM
33-45" TAN TO GRAY SILT INCONSISTENT
AROUND HOLE
45-83" TAN TO MED. TO FINE SAND W/GRAVEL
AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 44
0-6" TOPSOIL
6-14" BROWN FINE TO MED. SANDY LOAM
14-42" TAN TO GRAY SILT INCONSISTENT AROUND HOLE
42-102" TAN TO GRAY MED. TO FINE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 45
0-13" TOPSOIL
13"-23" BROWN FINE TO VERY FINE SANDY LOAM
23-37" GRAY FINE TO MED. SAND W/SILT
37-93" BROWN TO GRAY COARSE SAND W/
GRAVEL AND SOME COBBLES
MOTTLING @ 37"
NO WATER
NO LEDGE

TP 46
0-15" TOPSOIL
15-39" GRAY TO TAN VERY FINE SANDY W/SILT
39-51" GRAY FINE TO MED. SAND W/SILT & HEAVILY
MOTTLED THROUGHOUT
51-108" BROWN TO TAN COARSE SAND W/
GRAVEL AND SOME COBBLES
MOTTLING @ 39"
WATER @ 96"
NO LEDGE

TP 47
0-10" TOPSOIL
10-22" BROWN FINE TO MED. SANDY LOAM W/SILT
22-41" LIGHT BROWN TO ORANGE SILTY LOAM,
TRACE FINE SAND
41-98" BROWN TO GRAY COARSE SAND W/GRAVEL
AND SOME COBBLES
NO MOTTLING
WATER @ 96"
NO LEDGE

TP 48
0-10" TOPSOIL
10-28" BROWN FINE TO VERY FINE SANDY LOAM TO SILT
28-106" BROWN TO GRAY MED. TO COARSE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER-WET AT BOTTOM
NO LEDGE

TP 49
0-10" TOPSOIL
10-24" BROWN FINE TO VERY FINE SANDY LOAM
24-52" LIGHT YELLOW TO BROWN VERY
FINE SAND W/SILT
52-99" BROWN TO GRAY COARSE SAND WITH
GRAVEL, FEW COBBLES
POSSIBLE MOTTLING @ 52"
WATER @ 90"
NO LEDGE

TP 50
0-10" TOPSOIL
10-24" BROWN FINE TO VERY FINE SANDY LOAM
24-41" LIGHT YELLOW TO TAN VERY FINE SAND,
W/SILT
41-111" TAN TO BROWN COARSE SAND W/GRAVEL
AND SOME COBBLES
NO MOTTLING
WATER @ 106"
NO LEDGE

TP 51
0-10" TOPSOIL
10-20" LIGHT BROWN FINE TO VERY FINE
SANDY LOAM
20-42" LIGHT YELLOW TO BROWN VERY FINE
SAND W/TRACE SILT
42-101" BROWN TO TAN COARSE SAND WITH
GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 52
0-13" TOPSOIL
13-38" BROWN FINE TO VERY FINE SANDY LOAM
38-90" BROWN TO TAN COARSE TO MED. SAND
WITH SOME GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 53
0-13" TOPSOIL
13-32" BROWN FINE TO MED. SANDY LOAM
32-92" BROWN TO TAN COARSE TO
MED. SAND W/GRAVEL AND MANY COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 54
0-11" TOPSOIL
11-32" BROWN FINE TO VERY FINE SANDY LOAM
32-95" BROWN TO TAN COARSE TO MED. SAND
W/GRAVEL AND SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 55
0-14" TOPSOIL
14-22" BROWN FINE TO VERY FINE SANDY LOAM
22-37" LIGHT BROWN FINE TO VERY FINE SAND W/SILT
37-110" TAN MED. SAND W/GRAVEL, FEW COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 56
0-15" TOPSOIL
15-43" LIGHT BROWN SILTY LOAM, SOME FINE SAND
43-110" TAN MED. SAND SOME GRAVEL
FEW COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 57
0-8" TOPSOIL
8-27" LIGHT BROWN FINE TO VERY FINE SANDY LOAM
27-104" TAN TO GRAY MED. TO COARSE SAND
W/GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 58
0-12" TOPSOIL
12-33" LIGHT BROWN FINE TO VERY FINE SANDY LOAM
32-98" TAN TO BROWN MED. TO COARSE
SAND WITH GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 59
0-11" TOPSOIL
11-23" BROWN FINE TO VERY FINE SANDY LOAM
23-93" BROWN TO TAN COARSE TO MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 60
0-10" TOPSOIL
10-23" BROWN FINE TO VERY FINE SANDY LOAM
23-97" BROWN TO TAN COARSE TO MED.
SAND WITH GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 61
0-8" TOPSOIL
8-28" BROWN VERY FINE SANDY LOAM
28-99" TAN TO BROWN COARSE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 62
0-9" TOPSOIL
9-24" LIGHT BROWN VERY FINE SANDY LOAM
24-96" BROWN TO TAN COARSE TO MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 63
0-8" TOPSOIL
8-26" BROWN FINE TO MED. SANDY LOAM
26-91" BROWN TO TAN COARSE TO MED. SAND,
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 64
0-10" TOPSOIL
10-31" BROWN FINE SANDY LOAM
31-91" BROWN TO TAN COARSE TO MED.
SAND W/SOME SILT GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 65
0-13" TOPSOIL
13-30" LIGHT BROWN FINE TO VERY FINE SANDY LOAM
30-100" TAN TO BROWN COARSE SAND
WITH GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 66
0-10" TOPSOIL
10-28" BROWN FINE SANDY LOAM
28-90" TAN TO GRAY MED. TO COARSE
SAND W/SOME GRAVEL
NO MOTTLING
NO WATER
NO LEDGE

TP 67
0-14" TOPSOIL
14-25" LIGHT BROWN FINE TO VERY FINE SANDY LOAM
25-108" TAN TO BROWN MED. TO COARSE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 68
0-11" TOPSOIL
11-29" BROWN FINE TO MED. SANDY LOAM
29-80" TAN TO GRAY MED. TO COARSE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 69
0-12" TOPSOIL
12-36" YELLOW TAN FINE TO VERY FINE SANDY LOAM
36-93" TAN TO BROWN MED. TO FINE SAND
W/GRAVEL, SOME COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 70
0-14" TOPSOIL
14-36" BROWN FINE TO MED. SANDY LOAM
36-91" TAN TO GRAY MED. TO FINE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 71
0-8" TOPSOIL
8-36" BROWN FINE TO MED. SANDY LOAM
36-96" TAN TO GRAY MED. TO FINE
SAND W/ GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 72
0-8" TOPSOIL
8-31" LIGHT BROWN FINE TO MED. SANDY LOAM
32-91" TAN TO GRAY MED. TO FINE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 73
0-11" TOPSOIL
13-28" BROWN FINE SANDY LOAM
28-37" YELLOW TAN FINE TO VERY FINE
SANDY LOAM
37-90" TAN TO BROWN FINE TO MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 74
0-6" TOPSOIL
6-39" BROWN FINE SANDY LOAM
39-99" TAN TO BROWN FINE TO MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 75
0-10" TOPSOIL
10-29" LIGHT BROWN FINE SANDY LOAM
29-96" TAN TO OLIVE/BROWN FINE TO MED.
SAND W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 76
0-10" TOPSOIL
10-34" LIGHT BROWN FINE SANDY LOAM
34-96" TAN TO OLIVE/BROWN FINE TO MED.
SAND W/GRAVEL AND COBBLES STRATIFIED
NO MOTTLING
NO WATER
NO LEDGE

TP 77
0-11" TOPSOIL
11-36" BROWN FINE TO MED. SANDY LOAM
36-101" BROWN TO TAN MED. TO FINE
SAND WITH GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 78
0-15" TOPSOIL
15-46" BROWN FINE TO MED. SANDY LOAM
46-106" BROWN TO TAN MED. FINE SAND
W/ SOME GRAVEL
NO MOTTLING
NO WATER
NO LEDGE

TP 79
0-11" TOPSOIL
11-36" BROWN FINE TO MED. SANDY LOAM
38-90" TAN TO GRAY MED. TO FINE
SAND WITH GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 80
0-13" TOPSOIL
12-33" BROWN FINE TO MED. SANDY LOAM
33-95" TAN TO GRAY MED. TO FINE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 81
0-13" TOPSOIL
13-40" BROWN FINE TO MED. SANDY LOAM
40-96" TAN TO GRAY MED. SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
NO LEDGE

TP 82
0-9" SAND AND GRAVEL FILL
9-18" TOPSOIL
18-52" LIGHT BROWN FINE TO VERY FINE
SANDY LOAM, SOME SILT
52-101" TAN TO BROWN FINE TO MED.
SAND, SOME GRAVEL
NO MOTTLING
NO WATER
NO LEDGE

TP 83
0-9" TOPSOIL
9-31" BROWN FINE SANDY LOAM
31-104" TAN-BROWN COARSE SAND
WITH GRAVEL AND COBBLES
NO MOTTLING
NO WATER
LEDGE-NONE TO 104"

TP 84
0-11" TOPSOIL
11-38" BROWN FINE SANDY LOAM
38-92" TAN TO BROWN MED-COARSE
SAND W/GRAVEL AND COBBLES
NO MOTTLING
WATER @ 79"
LEDGE-NONE TO 92"

TP 85
0-12" TOPSOIL
12-33" BROWN FINE SANDY LOAM
30-98" TAN TO COARSE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
LEDGE-NONE TO 98"

TP 86
0-8" TOPSOIL
8-30" BROWN FINE SANDY LOAM
30-89" TAN COARSE SAND
W/GRAVEL AND COBBLES
NO MOTTLING
NO WATER
LEDGE-NONE TO 89"

PLAN SHOWING
DEEP TEST PIT DATA
RESUBDIVISION
PROPERTY OF
AVERY BROOK HOMES LLC
94, 96, 98 AND 100
STODDARDS WHARF ROAD
A.K.A.
CONNECTICUT ROUTE 214
LEDYARD, CONNECTICUT
JULY 2022



THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB#22-007.DWG FBK#327

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____

CHAIRMAN OR SECRETARY _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF _____ DATE _____
THE LEDYARD PLANNING AND ZONING COMMISSION ON _____

LOT NUMBERS ASSIGNED BY THE ASSESSOR _____

ASSESSOR _____ DATE _____

TWIC APPLICATION# _____
APPROVED, _____

NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)
NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA: NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)


WETLANDS OFFICER _____ DATE _____

APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.
PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION _____

CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION _____
ZONING ENFORCEMENT OFFICER _____ DATE _____




DIETER & GARDNER
LAND SURVEYORS • PLANNERS
1641 CONNECTICUT ROUTE 12
P.O. BOX 335
GALES FERRY, CT, 06335
(860) 464-7455
EMAIL: DIETER.GARDNER@YAHOO.COM



LEGEND

- STONE WALL
- PROPERTY LINE
- STREET LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- EDGE OF WETLANDS & FLAG NUMBER
- BUILDING SETBACK LINE
- LIMITS OF DISTURBANCE
- APPROXIMATE DEEP TEST PIT
- APPROXIMATE PERC TEST LOCATION
- UTILITY POLE
- CONCEPTUAL HOME
- CONCEPTUAL PRIMARY SEPTIC
- CONCEPTUAL RESERVE AREA
- CONCEPTUAL WELL
- TOPSOIL STOCKPILE
- HAYBALES/SILT FENCE/WOODCHIPS

NOTE: FOOTING DRAINS NOT REQUIRED OR PROPOSED.



PLAN SHOWING RESUBDIVISION PROPERTY OF AVERY BROOK HOMES LLC 94, 96, 98 AND 100 STODDARDS WHARF ROAD A.K.A. CONNECTICUT ROUTE 214 LEDYARD, CONNECTICUT
SCALE: 1"=40'
JULY 2022
REVISED: OCTOBER 31, 2022

I HAVE REVIEWED THE INLAND WETLAND BOUNDARY I DELINEATED AND I AM OF THE OPINION THAT THE WETLAND BOUNDARY IS SHOWN CORRECTLY ON THIS MAP.
Ian Cole
IAN COLE
SOIL SCIENTIST

THE WORD "CERTIFY" IS UNDERSTOOD TO BE AN EXPRESSION OF THE PROFESSIONAL OPINION BY THE LAND SURVEYOR WHICH IS BASED ON HIS OR HER BEST KNOWLEDGE, INFORMATION AND BELIEF, AS SUCH IT CONSTITUTES NEITHER GUARANTEE OR WARRANTY. THE STONE WALLS AND/OR FENCES SHOWN AS BOUNDARIES MAY HAVE IRREGULARITIES OF COURSE BETWEEN PRINCIPAL POINTS OF COURSE INDICATED.

© THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB# 22-007.DWG FBK#327

NOTE: BOUNDARY LINES OF ADJOINING PROPERTIES ARE SHOWN FOR GENERAL INFORMATIONAL PURPOSES ONLY AND ARE NOT TO BE CONSTRUED AS BEING ACCURATELY LOCATED OR DEPICTED.

TITLE: LAND SURVEYOR CT No. 14208
DATE: JULY 7, 2022

SANITARY DESIGN CRITERIA

- A. ALL PRIMARY AND SEPTIC SYSTEM DESIGNS ARE LAYED OUT FOR THREE-BEDROOM HOMES. NO TUBS OVER 100 GALLONS IN SIZE OR GARBAGE DISPOSAL INTO SEPTIC SYSTEM PLANNED.
 - B. THREE BEDROOM HOMES AT A PERC RATE OF 10.0 MIN/INCH OR LESS REQUIRES 495 S.F. OF EFFECTIVE LEACHING AREA.
 - C. GST 6236 LEACHING SYSTEM SELECTED FOR LEACHING SYSTEM DESIGN. MINIMUM REQUIRED AREA IS 495 S.F./ 26.2 S.F./L.F. = 18.9' UNLESS MLSS GOVERNS.
- HF = HYDRAULIC FACTOR BASED ON GRADIENT AND DEPTH TO RESTRICTION
 FF = FLOW FACTOR, 1.5 FOR THREE BEDROOM HOME DESIGN
 PF = PERC FACTOR, 1.0 PERCOLATION RATE UP TO 10.0 MIN/INCH.

MLSS TABLE								
LOT NUMBER	DESIGN PITS	GRADIENT	RESTRICTION	HF	FF	PF	MLSS	SYSTEM
1	1, 2, 3 & 4	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
2	9, 10, 11 & 12	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
3	13 & 14	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
4	15 & 16	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
5	17 & 18	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
6	21 & 22	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
7	85 & 86	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
8	27 & 28	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
9	29, 30, 31 & 32	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
10	33 & 34	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
11	35 & 36	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
12	37 & 38	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
13	81 & 82	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
14	39 & 40	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
15	41 & 42	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
16	43 & 44	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
17	51 & 52	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
18	53 & 54	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
19	55 & 56	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
20	47 & 48	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
21	61 & 62	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
22	69 & 70	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
23	75 & 76	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
24	73 & 74	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
25	65, 66, 67 & 72	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236
26	63 & 64	MLSS	NOT	APPLICABLE	1.5	1.0		20 L.F. GST 6236

LOT 1 27" DEEP		WATER QUALITY BASIN 29" DEEP		WATER QUALITY BASIN 30" DEEP		LOT 2 26" DEEP		LOT 2 26" DEEP		LOT 2 29" DEEP		LOT 3 30" DEEP		LOT 4 30" DEEP		LOT 5 29" DEEP	
TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING
8:59	2"	8:51	4"	9:00	2 1/2"	9:02	2 1/4"	9:55	2"	1:30	4"	1:32	4"	1:34	3"	1:41	4"
9:04	6 3/4"	8:56	10"	9:05	7 1/2"	9:07	13 1/2"	10:00	8 1/2"	1:35	20"	1:37	13"	1:39	9 1/2"	1:46	10"
9:09	9"	9:01	13 3/4"	9:10	11"	9:12	19"	10:05	13"	1:40	23"	1:42	18"	1:44	13"	1:51	13"
9:14	11"	9:06	16"	9:15	13 1/2"	9:17	22 1/2"	10:10	17"	1:45	24 1/2"	1:47	20 1/2"	1:49	15 1/2"	1:56	15 1/2"
9:19	12 1/2"	9:11	18"	9:20	16"	9:22	24 1/2"	10:15	19 1/2"	1:50	25 1/2"	1:52	23"	1:54	18"	2:01	17 1/2"
9:24	14"	9:16	20"	9:25	17 1/2"	9:27	26"	10:20	22"	1:55	26 1/2"	1:57	24"	1:59	20"	2:06	18"
9:29	15 1/2"	9:21	21"	9:30	19 1/2"	9:32	DRY	10:25	24"	2:00	27 1/2"	2:02	25"	2:04	21 1/2"	2:11	20 1/2"
9:34	17"	9:26	22"	9:35	20 1/2"	9:37	DRY	10:30	25"	2:05	28 1/2"	2:07	25 3/4"	2:09	23"	2:16	22"
9:39	18 1/4"	9:31	23"	9:40	21 1/2"	9:42	DRY	10:35	26"	2:10	DRY	2:12	26 3/4"	2:14	24 1/2"	2:21	23 1/2"
9:44	19 1/4"	9:36	24"	9:45	22 1/2"	9:47	DRY	10:40	DRY	2:15	DRY	2:17	27 3/4"	2:19	26"	2:26	25"
9:49	20 1/4"	9:41	25"													2:31	26 1/2"

LOT 6 27" DEEP		LOT 7 27" DEEP		LOT 7 27" DEEP		LOT 8 30" DEEP		LOT 9 32" DEEP		LOT 9 30" DEEP		LOT 10 30" DEEP		LOT 11 28" DEEP	
TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING
9:13	4"	9:10	4"	9:18	3"	11:28	4"	11:24	3 1/2"	10:41	9"	10:39	7"	10:45	3"
9:18	11 1/2"	9:15	14 1/2"	9:23	7"	11:33	10"	11:29	17 1/2"	10:46	12 1/2"	10:44	11"	10:44	12"
9:23	16"	9:20	17 1/2"	9:28	10"	11:38	12 1/2"	11:34	21"	10:51	15"	10:49	15"	10:55	14 1/4"
9:28	18"	9:25	19 1/2"	9:33	13 3/4"	11:43	14 1/2"	11:39	23 1/2"	10:56	17"	10:54	19 1/2"	11:00	15 1/4"
9:33	20"	9:30	22"	9:38	13"	11:48	16 1/2"	11:44	25 1/2"	11:01	19"	10:59	20 1/2"	11:05	17 1/4"
9:38	21 1/2"	9:35	23"	9:43	14 1/4"	11:53	17 1/4"	11:49	27 1/2"	11:06	19 1/2"	11:04	22"	11:10	19 1/4"
9:43	22"	9:40	24"	9:48	15 1/4"	11:58	19"	11:54	29"	11:11	20 1/2"	11:09	23"	11:15	21"
9:48	23 1/2"	9:45	25"	9:53	16 1/2"	12:03	20 1/2"	11:59	30 1/2"	11:16	21 1/2"	11:14	24"	11:20	22 1/4"
9:53	24 1/2"	9:50	26"	9:58	17 7/8"	12:08	21 1/8"	11:21	22 1/2"	11:19	22 1/2"	11:19	25"	11:25	23 1/4"
9:58	25 1/2"	9:55	DRY	10:03	19 1/2"			12:04	DRY	11:26	23 1/2"	11:24	25 3/4"	11:30	24 1/2"
10:03	DRY													11:35	25 3/4"

LOT 12 28" DEEP		LOT 13 27" DEEP		LOT 14 27" DEEP		LOT 15 29" DEEP		LOT 16 26" DEEP		LOT 17 29" DEEP		LOT 18 30" DEEP		LOT 19 29" DEEP		LOT 19 30" DEEP	
TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING
10:37	3"	8:48	2"	8:41	4"	8:43	5"	8:40	5 1/2"	1:50	4 1/4"	1:30	2 1/2"	10:49	3"	1:27	2 1/2"
10:42	6 3/4"	8:53	9"	8:46	8 1/4"	8:48	10 3/4"	8:45	9 1/2"	1:55	11 7/8"	1:35	9 1/2"	10:54	11"	1:32	8 1/4"
10:47	9 1/4"	8:58	14"	8:51	10 1/4"	8:53	15"	8:50	15 1/2"	2:00	15 1/2"	1:40	13 1/2"	10:59	15"	1:37	13"
10:52	12 1/2"	9:03	18"	8:56	12 1/2"	8:58	17 1/2"	8:55	14"	2:05	18"	1:45	15"	11:04	18 1/2"	1:42	15 1/2"
10:57	15"	9:08	20"	9:01	15"	9:03	19 1/2"	9:00	15 1/2"	2:10	21"	1:50	17 1/2"	11:09	20 1/2"	1:47	18"
11:02	17"	9:13	22"	9:06	17"	9:08	21"	9:05	16 1/2"	2:15	23"	1:55	20"	11:14	22"	1:52	19 1/2"
11:07	19"	9:18	23"	9:11	18"	9:13	22"	9:10	17 3/4"	2:20	25"	2:00	21 1/2"	11:19	23 1/2"	1:57	21 1/2"
11:12	20"	9:23	24"	9:16	19"	9:18	23"	9:15	18 1/2"	2:25	27"	2:05	22 1/2"	11:24	25"	2:02	23"
11:17	21"	9:28	25"	9:21	20"	9:23	23 3/4"	9:20	19 1/2"	2:30	28 7/8"	2:10	23 1/2"	11:29	26 1/2"	2:07	24 1/2"
11:22	22 1/8"	9:33	26"	9:26	21"	9:28	24 1/2"	9:25	20 1/2"	2:35	DRY	2:15	24 1/2"			2:12	26"
11:27	23 1/8"	9:38	DRY	9:31	22"	9:33	25 1/2"	9:30	21 1/2"								

LOT 20 28" DEEP		LOT 21 30" DEEP		LOT 22 29" DEEP		LOT 22 28" DEEP		LOT 23 28" DEEP		LOT 23 29" DEEP		LOT 24 28" DEEP		LOT 25 29" DEEP		LOT 26 30" DEEP	
TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING	TIME	READING
1:38	5"	10:18	2 1/2"	11:46	3"	10:15	3"	11:23	3"	11:45	3"	12:27	3"	12:30	3"	11:43	3 1/2"
1:43	11"	10:23	12"	11:51	6 1/2"	10:20	11 1/2"	11:28	11 3/4"	11:50	7 3/4"	12:32	7 1/2"	12:35	12"	11:48	8"
1:48	13 1/2"	10:28	15 1/2"	11:56	9"	10:25	16 1/2"	11:33	15"	11:55	11 1/2"	12:37	11 1/2"	12:40	17 1/2"	11:53	10"
1:53	16"	10:33	19 1/2"	12:01	12"	10:30	21"	11:38	18"	12:00	13 3/4"	12:42	14"	12:45	20"	10:58	13"
1:58	16"	10:38	21"	12:06	13 1/2"	10:35	24"	11:43	21 1/2"	12:05	16"	12:47	16"	12:50	23"	12:03	14 1/2"
2:03	19"	10:43	22 1/2"	12:11	14 1/2"	10:40	25 1/2"	11:48	24"	12:10	18"	12:52	18"	12:55	25"	12:08	16"
2:08	20 1/8"	10:48	24"	12:16	16"	10:45	27"	11:53	26"	12:15	20"	12:57	19"	1:00	26 1/2"	12:13	17"
2:13	21 1/2"	10:53	25"	12:21	17 1/2"	10:50	DRY	11:58	DRY	12:20	21"	1:02	20"	1:05	28"	12:18	18 1/2"
2:18	22 1/2"	10:58	25 3/4"	12:26	18 1/2"					12:25	22 1/4"	1:07	21"	1:10	DRY	12:23	20"
2:23	23 1/2"	11:03	26 3/4"	12:31	19 1/2"					12:30	23 1/2"	1:12	22"			12:28	21"
2:28	24 1/2"			12:36	20 1/2"					12:35	25"						

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____

CHAIRMAN OR SECRETARY _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____

LOT NUMBERS ASSIGNED BY THE ASSESSOR

ASSESSOR _____ DATE _____

I/FWC APPLICATION# _____

APPROVED, _____

NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)

NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA; NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)

WETLANDS OFFICER _____ DATE _____

APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.

PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION

CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION

ZONING ENFORCEMENT OFFICER _____ DATE _____

PLAN SHOWING
 PERCOLATION TEST DATA,
 SEPTIC SYSTEM DESIGN CRITERIA
 AND
 MINIMUM LEACHING SYSTEM SPREAD
 RESUBDIVISION
 PROPERTY OF
 AVERY BROOK HOMES LLC
 94, 96, 98 AND 100
 STODDARDS WHARF ROAD
 A.K.A.
 CONNECTICUT ROUTE 214
 LEDYARD, CONNECTICUT


DIETER & GARDNER
 LAND SURVEYORS + PLANNERS
 1641 CONNECTICUT ROUTE 12
 P.O. BOX 335
 GALES FERRY, CT. 06335
 (860) 464-7455
 EMAIL: DIETER.GARDNER@YAHOO.COM

© THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB#22-007.DWG FBK#327

JULY 2022
 REVISED: OCTOBER 31, 2022

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____

CHAIRMAN OR SECRETARY _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____

LOT NUMBERS ASSIGNED BY THE ASSESSOR _____ DATE _____

ASSESSOR _____ DATE _____

IWWC APPLICATION# _____ DATE _____

APPROVED _____ DATE _____

NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)

NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA. NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)

WETLANDS OFFICER _____ DATE _____

APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT. _____ DATE _____

PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____ DATE _____

EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____


CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____ DATE _____

APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION _____ DATE _____

ZONING ENFORCEMENT OFFICER _____ DATE _____



DIETER & GARDNER
LAND SURVEYORS • PLANNERS
P.O. BOX 335
1641 CONNECTICUT ROUTE 12
GALES FERRY, CT. 06335
(860) 464-7455
EMAIL: DIETER.GARDNER@YAHOO.COM





DEEP TEST PIT DATA

TP 19	TP 20
0-14" TOPSOIL	0-17" TOPSOIL
14-36" BROWN FINE SANDY LOAM W/SILT	17-31" BROWN FINE SANDY LOAM W/SILT
36-84" TAN/GRAY COARSE SAND W/GRAVEL	31-83" TAN/GRAY COARSE SAND W/GRAVEL AND FEW COBBLES
MOTTLING @ 40" WATER @ 43" NO LEDGE	MOTTLING @ 43" WATER @ 46" NO LEDGE

LANDSCAPE SCHEDULE

TYPE	SYMBOL	QTY.	BOTANICAL NAME	COMMON NAME	METHOD	SIZE	REMARKS
PERENNIALS	EF	CLUSTER	EUPATORIUM FISTULOSUM	JOE PYE WEED	CONTAINER	1'-2" HEIGHT	UNIFORM WELL DEVELOPED PLANT 2' ON CENTER
GRASSES	PV	3	PANICUM VIRGATUM	SWITCH GRASS	CONTAINER	2'-3" HEIGHT	UNIFORM WELL DEVELOPED PLANT 2' ON CENTER
SHRUBS	IG	7	ILEX GLABRA	INKBERRY	B&B	3'-4' HEIGHT	AS SHOWN
	VA	17	VACCINIUM ANGUSTIFOLIUM	LOWBUSH BLUEBERRY	CONTAINER	12"-18" HT	AS SHOWN
TREES	BN	4	BETULA NIGRA	RIVER BIRCH	B&B	2 1/2"-3" CAL	MULTI-STEMMED AS SHOWN




- LEGEND
- STONE WALL
 - PROPERTY LINE
 - STREET LINE
 - EXISTING CONTOUR
 - PROPOSED CONTOUR
 - UTILITY POLE
 - LOT NUMBER
 - PROPOSED CATCH BASIN
 - EDGE OF WETLANDS & FLAG NUMBER
 - HAYBALES/SILT FENCE/WOODCHIPS
 - APPROXIMATE DEEP TEST PIT


I HAVE REVIEWED THE INLAND WETLAND BOUNDARY I DELINEATED AND I AM OF THE OPINION THAT THE WETLAND BOUNDARY IS SHOWN CORRECTLY ON THIS MAP.

Ian Cole

IAN COLE
SOIL SCIENTIST







PLAN / PROFILE
SHOWING
PROPERTY OF
AVERY BROOK HOMES LLC
STODDARDS WHARF ROAD
LEDYARD, CONNECTICUT
SCALE: 1" = 40' HORIZ.
1" = 4' VERT.
JULY 2022
REVISED: OCTOBER 31, 2022



© THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB#22-007.DWG FBK#327

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND.	
ALL IMPROVEMENTS SHALL BE COMPLETED BY _____	DATE _____
CHAIRMAN OR SECRETARY _____	DATE _____
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF _____	
THE LEDYARD PLANNING AND ZONING COMMISSION ON _____	DATE _____
LOT NUMBERS ASSIGNED BY THE ASSESSOR	
ASSESSOR _____	DATE _____
IWVC APPLICATION# _____	
APPROVED _____	
NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)	
NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA; NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)	
WETLANDS OFFICER _____	DATE _____
APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.	
PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____	DATE _____
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION	
CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____	DATE _____
APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION	
ZONING ENFORCEMENT OFFICER _____	DATE _____



LEGEND


○○○○○○○○	STONE WALL
— — — — —	PROPERTY LINE
— — — — —	STREET LINE
- - - - -	EXISTING CONTOUR
— — — — —	PROPOSED CONTOUR
⊙	UTILITY POLE

SIGHTLINE
DEMONSTRATION PLAN
PROPERTY OF
AVERY BROOK HOMES LLC
STODDARDS WHARF ROAD
LEDYARD, CONNECTICUT
SCALE: 1"=40' HORIZ.
1"=4' VERT.
JULY 2022
REVISED: OCTOBER 31, 2022


DIETER & GARDNER
LAND SURVEYORS • PLANNERS
P.O. BOX 335
1641 CONNECTICUT ROUTE 12
GALES FERRY, CT. 06335
(860) 464-7455
EMAIL: DIETER.GARDNER@YAHOO.COM

© THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN. JOB#22-007.DWG FBK#327

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____	
CHAIRMAN OR SECRETARY _____	DATE _____
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____	
LOT NUMBERS ASSIGNED BY THE ASSESSOR _____	
ASSESSOR _____	DATE _____
IWVC APPLICATION# _____	APPROVED, _____
NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)	
NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA: NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)	
WETLANDS OFFICER _____	DATE _____
APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT. _____	
PUBLIC WORKS DIRECTOR/TOWN ENGINEER _____	DATE _____
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION _____	
CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION _____	DATE _____
APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION _____	
ZONING ENFORCEMENT OFFICER _____	DATE _____




TYPICAL PAVED COMMON DRIVEWAY CROSS-SECTION
NOT TO SCALE




- ALL MATERIAL THICKNESS ARE FOR COMPACTED DEPTH
- IF BINDER COURSE IS LEFT AS A TOP COURSE FOR AN EXTENDED PERIOD, THE DIR OF PUBLIC WORKS MAY REQUIRE THAT A TACK COAT OF BITUMINOUS MATERIAL MAY BE APPLIED BEFORE LAYING THE BITUMINOUS CONCRETE SURFACE COURSE.
- SUBBASE DEPTH SHALL BE INCREASED TO 18" WHERE LEDGE ROCK IS ENCOUNTERED.
- FOR CONSTRUCTION MATERIAL STANDARDS, REFER TO STATE OF CONNECTICUT, STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION, FORM 613, AS AMENDED.

AVERY BROOK CIRCLE CROSS SECTION
(N.T.S.)




PLAN VIEW




SECTION VIEW
PREFORMED SCOUR HOLE

FE UNIT - USE MODIFIED RIPRAP (5')
NOT TO SCALE
FOR FLARED END UNIT




PLAN VIEW



SECTION VIEW
PREFORMED SCOUR HOLE


NOT TO SCALE




WATER QUALITY BASIN
(N.T.S.)

NOTES:
THE PURPOSE OF THE WATER QUALITY BASIN IS TO REMOVE SEDIMENT FROM THE WATER QUALITY VOLUME (WQV). THE BASIN IS SIZED TO HOLD THE WQV (3,600 CUBIC FEET) WHICH WILL BE FILTERED THROUGH THE SURFACE DRAIN AND SLOWLY RELEASED INTO THE WETLANDS.
STORMS THAT EXCEED THE WATER QUALITY VOLUME WILL FLOW OUT THE SPILLWAY.

D-BOX OUTLET
EXTENDED DETENTION
UNDERDRAIN OUTLET
NOT TO SCALE




EXTENDED DETENTION UNDERDRAIN
NOT TO SCALE



DRAINAGE PIPE TRENCH
NOT TO SCALE


NOTE:
1. IF PIPE IS PLACED IN OR ON LEDGE, ALL LEDGE WITHIN 12" OF PIPE SHALL BE REMOVED AND REPLACED WITH PIPE BEDDING.



SECURE TO 1 1/2" GALVANIZED STEEL POST WITH (2) 1/4" GALVANIZED BOLTS (1 TOP, 1 BOTTOM)

NOTE:
SIGN TO BE INSTALLED IN ACCORDANCE WITH STATE OF CONNECTICUT D.D.T. STANDARDS

STOP SIGN
NOT TO SCALE



PRECAST CATCH BASIN
NOT TO SCALE

- NOTES:
- IN PRECAST RISER SECTIONS, THE KNOCKOUTS OR OPENINGS AROUND THE PIPES SHALL BE MORTARED TO 6".
 - PRECAST REDUCER SHALL BE SPECIFICALLY SIZED & PLACED FOR THE TYPE OF TOP USED.
 - PLACE ALL PRECAST UNITS, TOPS AND CONCRETE BLOCKS IN A CEMENT MORTAR BED.
 - PRECAST UNITS SHALL BE REINFORCED WITH WELDED WIRE FABRIC.

DIETER & GARDNER
LAND SURVEYORS • PLANNERS
P.O. BOX 335
1641 CONNECTICUT ROUTE 12
GALES FERRY, CT. 06335
(860) 464-7455
EMAIL: DIETER.GARDNER@YAHOO.COM

PLAN SHOWING
CONSTRUCTION DETAILS
RESUBDIVISION
PROPERTY OF
AVERY BROOK HOMES LLC
94, 96, 98 AND 100
STODDARDS WHARF ROAD
A.K.A.
CONNECTICUT ROUTE 214
LEDYARD, CONNECTICUT

JULY 2022
REVISED: OCTOBER 31, 2022

© THIS DRAWING IS THE PROPERTY OF THE LAND SURVEYOR. THIS PLAN AND REPRODUCTIONS, ADDITIONS OR REVISIONS OF THIS PLAN ARE NOT VALID WITHOUT THE EMBOSSED SEAL AND SIGNATURE OF THE LAND SURVEYOR WHO PREPARED THIS PLAN.
JOB# 22-007.DWG

EROSION & SEDIMENT CONTROL PLAN

NARRATIVE:

PURPOSE AND DESCRIPTION OF PROJECT.

THE PURPOSE OF THIS PROJECT IS TO SUBDIVIDE 9.21 ACRES OF LAND TO CREATE 26 RESIDENTIAL BUILDING LOTS. EACH LOT WILL BE SERVICED BY ON SITE WELL AND SEPTIC SYSTEM. APPROXIMATELY 1330 LINEAR FEET OF ROAD WILL BE CONSTRUCTED. THE PAVEMENT WIDTH IS 22 FEET. THE TOTAL AREA OF NEW PAVEMENT ASSOCIATED WITH THE ROAD CONSTRUCTION WILL BE 30,400± SQUARE FEET. ROAD DRAINAGE HAS BEEN DESIGNED BY A PROFESSIONAL ENGINEER, AND INCLUDES IN PLACES CURBED PAVEMENT AND CATCH BASINS WITH 2 FOOT SUMP DEPTHS. THE UPLANDS ARE GENTLY SLOPING AND MOSTLY OLD PASTURE. THE UPLAND SOILS ON THE PROJECT SITE INCLUDE WELL DRAINED CANTON HINCKLEY AND AGAWAM SOILS.

IT IS ANTICIPATED THAT ONCE WORK ON THE PUBLIC IMPROVEMENTS BEGINS, IT WILL CONTINUE UNTIL THE PROJECT IS COMPLETED. IT IS ANTICIPATED THAT THE ROAD CONSTRUCTION WILL BE COMPLETED WITHIN ONE YEAR OF COMMENCEMENT.

PETER GARDNER 860-464-7455 (OR OWNER AT TIME OF CONSTRUCTION) SHALL BE RESPONSIBLE FOR OVERSEEING THE INSTALLATION AND PROPER MAINTENANCE OF ANY EROSION & SEDIMENT CONTROL MEASURES EMPLOYED IN IMPLEMENTING THIS PLAN.

TOTAL AREA OF THE PROJECT SITE AND THE TOTAL AREA OF THE SITE THAT IS EXPECTED TO BE DISTURBED BY ROAD AND DRAINAGE CONSTRUCTION ACTIVITIES.

THE TOTAL PROJECT AREA IS 9.21 ACRES OF WHICH 0.9± ACRES WILL BE DISTURBED TO FACILITATE THE CONSTRUCTION OF THE ROAD AND DRAINAGE.

ESTIMATE OF TOTAL AREA TO BE DISTURBED 3.9± ACRES FOR HOME/DRIVE AND SEPTIC CONSTRUCTION.

PLANNED START AND COMPLETION DATES FOR THE PROJECT.

IT IS ANTICIPATED THAT THE PROJECT WILL COMMENCE DURING FALL/WINTER OF 2022/2023 AND BE COMPLETED IN THE FALL OF 2023.

DESIGN CRITERIA, CONSTRUCTION DETAILS AND MAINTENANCE PROGRAM FOR THE EROSION & SEDIMENT CONTROL MEASURES TO BE USED.

SILT FENCE AND SILT FENCE BACKED WITH HAY BALES FOR STRUCTURAL SUPPORT WILL BE USED. ALL SILT FENCE SEDIMENT BARRIERS SHALL BE MAINTAINED SUCH THAT SEDIMENTS WILL BE REMOVED WHEN REACHING A HEIGHT OF 0.5 FEET. BREACHES IN SILT FENCE SHALL BE REPAIRED IMMEDIATELY. THE SILT FENCE SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RAINFALL OF 0.5 INCH IN A 24 HOUR PERIOD.

CONSTRUCTION ENTRANCE DESIGN AND MAINTENANCE CRITERIA FROM 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL. ENTRANCE. THE CONSTRUCTION ENTRANCES WILL BE CONSTRUCTED OF ANGULAR STONE IN A SIZE AND GRADATION CORRESPONDING TO ASTM C-33, SIZE NO. 2 OR 3, OR DOT STANDARD SPECIFICATIONS SECTION M.01.01 SIZE #3. THE CONSTRUCTION ENTRANCE WILL BE 12 FEET WIDE AND 50 FEET LONG.

CONSTRUCTION: CONSTRUCTION ENTRANCES AREA WILL BE CLEARED AND GRUBBED. AREAS WILL THEN BE ROUGH GRADED. A 4-INCH LAYER OF CRUSHED STONE WILL BE SPREAD AS DEPICTED IN THE DETAILS.

MAINTENANCE: THE CONSTRUCTION ENTRANCE WILL BE MAINTAINED IN A CONDITION THAT WILL MITIGATE TRACKING AND WASHING OF SEDIMENT ONTO PAVED SURFACES. THE CONSTRUCTION ENTRANCE WILL BE TOP DRESSED AS NEEDED TO PROVIDE FUNCTIONALITY. ADDITIONAL LENGTH MAY BE ADDED IF ON-SITE CONDITIONS WARRANT SUCH EXTENSION. ANY ACCUMULATED OR SPILLED SEDIMENTS WILL BE CLEANED IMMEDIATELY, AND DISPOSED OF IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THIS EROSION & SEDIMENT CONTROL PLAN.

STOCKPILE MANAGEMENT WILL BE DONE IN ACCORDANCE WITH THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL. (CHAPTER 4). TOPSOIL STOCKPILES WILL BE LOCATED AS DEPICTED ON THE PLANS, AND WILL BE TREATED AS DISTURBED GROUND, I.E.: SURROUNDED BY SILT FENCE, AND SEEDED TO GRASS AFTER ALL THE TOPSOIL TO BE STRIPPED IS PLACED IN THE STOCKPILE. STOCKPILE SLOPES SHALL NOT EXCEED 2:1.

TOPSOILING SHALL TAKE PLACE AS AREAS ARE BROUGHT TO GRADE. THE TOPSOIL THAT SHALL BE SPREAD IS OF NATURAL ORIGIN AND WILL BE TAKEN FROM THE TOPSOIL STOCKPILE(S) REFERRED TO ABOVE. STONES LARGER THAN 2 INCHES IN DIAMETER AND OTHER DEBRIS WILL BE REMOVED FROM THE TOPSOIL WITH A RAKE. TOPSOIL SHALL BE SPREAD AT A MINIMUM DEPTH OF 4 INCHES OVER ALL DISTURBED AREAS. IN ORDER TO "BOND" THE TOPSOIL TO THE SUBSOIL, THE SUBGRADE WILL BE LOOSENEED BY "TRACKING" WITH A BULLDOZER IMMEDIATELY BEFORE APPLYING TOPSOIL. TOPSOIL WILL NOT BE PLACED IF THE SUBGRADE OR THE TOPSOIL IS FROZEN OR TOO WET. HEAVY RUBBER-TIRED VEHICLES WILL BE EXCLUDED FROM THE NEWLY TOPSOILED AREAS TO PREVENT EXCESSIVE COMPACTION WHICH COULD HINDER SEED GERMINATION AND SEEDLING GROWTH.

PERMANENT SEEDING WILL BE DONE AS DISTURBED AREAS ARE BROUGHT TO GRADE AND TOPSOILED AS LONG AS SUCH SEEDING IS DONE BETWEEN APRIL 1 AND JULY OR AUGUST 15 THROUGH OCTOBER 31. WITHIN 7 DAYS AFTER TOPSOIL IS APPLIED THE APPROPRIATE SEED MIX WILL BE BROADCAST AT THE PRESCRIBED RATE FOR THAT PARTICULAR MIX. THE SELECTED SEED MIX WILL BE FROM THE 2002 CONNECTICUT GUIDELINES FOR EROSION AND SEDIMENT CONTROL, FIGURE PS-3. PRIOR TO SEEDING, FERTILIZER WILL BE APPLIED AT THE RATE OF 7.5 PER 1,000 SQUARE FEET (10-10-10 OR EQUIVALENT), AND GROUND LIMESTONE WILL BE APPLIED AT THE RATE OF 200 POUNDS PER 1,000 SQUARE FEET. THE LIME AND FERTILIZER WILL BE LIGHTLY WORKED TO A DEPTH OF 3 TO 4 INCHES. SEED SHALL BE APPLIED UNIFORMLY USING A CYCLONE SEEDER (HYDROSEEDING MAY BE USED IN LIEU OF CONVENTIONAL SEEDING METHODS) HAY MULCH WILL BE APPLIED AT THE RATE OF 100 POUNDS (APPROXIMATELY 2 BALES) PER 1,000 SQUARE FEET. WHERE SLOPES EXCEED 10 PERCENT, JUTE NETTING SHALL BE USED TO ANCHOR THE HAY MULCH IN PLACE. ANY SUCH NETTING WILL BE INSTALLED TO MANUFACTURER'S RECOMMENDATIONS.

MAINTENANCE: THE SEEDBED WILL BE INSPECTED AT LEAST ONCE PER WEEK, AND WITHIN 24 HOURS OF A RAINFALL IN AN AMOUNT EXCEEDING 0.5 INCHES IN 24 HOURS. IN ANY AREAS THAT SUSTAIN DAMAGE, THE TOPSOIL WILL BE REAPPLIED AND "SMOOTHED," AND RESEED AS DESCRIBED ABOVE. THE NEWLY ESTABLISHED GRASS WILL NOT BE MOWN UNTIL IT REACHES A HEIGHT OF 6 INCHES. MOWING WILL NOT TAKE PLACE WHEN THE GROUND SURFACE IS WET. THE FIRST MOWING WILL TAKE 33 TO 50 PERCENT OF THE GRASS HEIGHT (I.E.: NOT BELOW 3 INCHES). MULCH MATERIALS WILL NOT BE REMOVED, BUT WILL BE ALLOWED TO DISINTEGRATE OVER TIME.

WHERE BARE GROUND NEEDS TO BE PROTECTED FOR RELATIVELY SHORT PERIODS, OR WHERE THE SEEDING SEASONS FOR PERMANENT SEEDINGS CAN NOT BE ADHERED TO, TEMPORARY SEEDING MAY BE USED. THE RECOMMENDED SEED MIX WILL VARY UPON CIRCUMSTANCES, BUT SHALL BE IN COMPLIANCE WITH THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL, FIGURE TS-2, TEMPORARY SEEDING RATES AND DATES. WHERE THE SEASON PRECLUDES ANY TYPE OF SEEDING, AN ANCHORED MULCH WILL BE EMPLOYED TO PROTECT BARE SOIL AREAS.

CONSTRUCTION SEQUENCE. PRIOR TO THE COMMENCEMENT OF ANY EARTH DISTURBANCES, THE DEVELOPER AND HIS CONTRACTOR SHALL MEET WITH TOWN STAFF FOR A PRECONSTRUCTION CONFERENCE.

- 1) INSTALL CONSTRUCTION ENTRANCE AS SHOWN ON PLAN.
- 2) INSTALL EROSION AND SEDIMENT CONTROL.
- 3) CONSTRUCT THE STORMWATER QUALITY BASIN. TOPSOIL WILL BE APPLIED TO THE BASIN SIDESLOPES IMMEDIATELY AFTER CONSTRUCTION, AND THE SIDESLOPES WILL BE SEEDED INSTALL SEDIMENT BARRIERS ALONG THE ROAD AND IN THE AREA OF THE BASIN AS DEPICTED ON THE PLANS.
- 4) STRIP TOPSOIL FROM THE ROADWAY AND STOCKPILE TOPSOIL ACCORDING TO THE PLAN. SEED STRIPPED AREAS THAT ARE NOT TO BE WORKED FOR 30 DAYS IMMEDIATELY WITH PERENNIAL RYEGRASS AT THE RATE OF 40 LBS./ACRE.
- 5) GRADE THE ROAD TO ATTAIN THE PLANNED SUBGRADE PROFILE AND GRADE SIDESLOPES TO PLAN.
- 6) APPLY TOPSOIL AND PERMANENT SEED MIX AND APPLY AND ANCHOR MULCH TO ALL FINISHED SLOPES.
- 7) INSTALL ALL DRAINAGE STARTING AT THE OUTFALL AND PROCEEDING UPGRADIENT. THE CONTRACTOR WILL ENSURE THAT ADEQUATE FLOW IS PROVIDED AT THE OUTFALL OF THE DRAINAGE SYSTEM SO THAT SEDIMENTS WILL BE PREVENTED FROM MIGRATING OFF THE SITE. NO WATER WILL BE ALLOWED TO ENTER THE DRAINAGE SYSTEM UNTIL THE OUTFALL IS PROTECTED. ALL DRAINAGE COMPONENTS WILL BE CHECKED ON A REGULAR BASIS AND CLEANED AS NEEDED TO MAINTAIN PROPER FUNCTION.
- 8) PLACE, GRADE AND COMPACT THE SUBGRADE AGGREGATE TO ESTABLISH THE ROADWAY BASE. TOPSOIL AND GRADE ALL SLOPES/DISTURBED AREAS WITHIN 2 FEET OF THE OUTSIDE OF THE PROPOSED CURBS.
- 9) LAY DOWN FIRST COURSE OF BITUMINOUS PAVEMENT.
- 10) INSTALL CURBING (WHERE REQUIRED).
- 11) APPLY TOP COURSE OF BITUMINOUS PAVEMENT.
- 12) REMOVE SILT FENCE AFTER TOPSOIL STABILIZED.

DISPOSAL OF SEDIMENTS - ANY SEDIMENT REMOVED FROM ANY EROSION AND SEDIMENT CONTROL MEASURE AS PART OF SITE MAINTENANCE SHALL BE DISPOSED OF IN A MANNER CONSISTENT WITH THE INTENT OF THIS PLAN. NO SEDIMENT SHALL BE DEPOSITED IN ANY WETLAND AREA.

FIELD CHANGES - IF FIELD MODIFICATIONS OF PLANNED MEASURES ARE NEEDED TO PROPERLY ADDRESS ANY EROSION OR SEDIMENTATION SITUATION, SUCH CHANGES MAY BE MADE ONLY AFTER NOTIFYING TOWN STAFF. ADDITIONAL NON-STRUCTURAL MEASURES MAY BE ADDED WITHOUT PRIOR NOTIFICATION.

STORMWATER QUALITY BASIN CONSTRUCTION NOTES:

1. STORMWATER QUALITY BASIN EMBANKMENTS SHALL BE CONSTRUCTED OF SILTY SAND AND/OR CLAYEY MATERIALS. ON-SITE BORROW MATERIAL MAY BE USED IF SUITABLE DEPOSITS ARE FOUND. EMBANKMENT FILL SHALL CONTAIN AT LEAST 15% BY WEIGHT OF MATERIAL PASSING THE #200 SIEVE AND NOT MORE THAN 50% PASSING THE #20 SIEVE.
2. EMBANKMENT FILL SHALL HAVE NO STONES LARGER THAN 6" IN THEIR GREATEST DIMENSION. NO STONES LARGER THAN 2" IN THEIR GREATEST DIMENSION SHALL BE ALLOWED WITHIN 2 FEET OF STRUCTURES OR PIPES.
3. ALL FILL MATERIAL SHALL BE FREE OF TOPSOIL, ROOTS, STUMPS, ORGANICS, FROZEN MATERIAL AND OTHER DELETERIOUS MATTER.
4. ALL EMBANKMENT MATERIAL SHALL BE COMPACTED TO 95% MINIMUM RELATIVE COMPACTIONS DETERMINED BY ASTM D1557 - MODIFIED PROCTOR. THE MAXIMUM LOOSE LIFT THICKNESS OF EMBANKMENT FILL SHALL BE 12".
5. ALL TOPSOIL, ORGANICS, ROOTS AND OTHER DELETERIOUS MATTER SHALL BE REMOVED FROM THE EXISTING GROUND SURFACE PRIOR TO CONSTRUCTION OF THE PROPOSED EMBANKMENTS.
6. ALL EMBANKMENTS AND DISTURBED AREAS OF THE STORMWATER QUALITY BASIN SHALL BE PERMANENTLY STABILIZED WITH 4" LOAM. SEED AND MULCH, SUITABLE HYDROSEEDING EQUIPMENT MAY BE USED FOR APPLICATION OF SEED, MULCH AND/OR FERTILIZER. THE FOLLOWING SEED MIX SHALL BE USED IN THESE AREAS.

VARIETY	LBS./ACRE
CREeping RED FESCUE	20
REDTOP	2
BENT GRASS	15
	TOTAL 37





STORMWATER QUALITY BASIN OPERATION AND MAINTENANCE NOTES:

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL MAINTENANCE AND INSPECTIONS PRIOR TO COMPLETION OF THE ROADWAY.
2. DURING THE FIRST YEAR OF OPERATION, THE BASIN SHALL BE INSPECTED ON WEEKLY BASIS OR WITHIN 24 HOURS AFTER A RAINFALL EVENT OF 0.5 INCH OR GREATER. ANY EROSION OF EMBANKMENTS OR OUTLET AREAS SHALL BE REPAIRED PROMPTLY. ANY DEBRIS SHALL BE REMOVED AND DISPOSED OF. SEDIMENTATION THAT WOULD INTERFERE WITH PROPER OPERATION OF THE BASIN SHALL BE REMOVED AND DISPOSED OF AND THE AREA RESTORED AND STABILIZED AS REQUIRED.
3. AFTER THE BASIN HAS BEEN IN OPERATION FOR ONE YEAR, INSPECTIONS SHALL BE PERFORMED QUARTERLY OR WITHIN 24 HOURS AFTER A STORM EVENT OF 2.0 INCHES OR GREATER. QUARTERLY INSPECTIONS SHALL INCLUDE THE FOLLOWING ITEMS:
 - NOXIOUS WEEDS SHALL BE REMOVED. PERFORM ANY MOWING OPERATIONS REQUIRED.
 - INSPECT EMBANKMENTS FOR ANY WOODY GROWTH. ALL TREES, VINES AND OTHER WOODY PLANTS SHALL BE REMOVED AND VOIDS LEFT FROM THEIR REMOVAL SHALL BE REPAIRED.
 - INSPECT EMBANKMENTS FOR ANY ANIMAL BURROWS. ALL BURROWS AND VOIDS SHALL BE REPAIRED IMMEDIATELY.
 - ACCUMULATED SEDIMENT SHALL BE REMOVED FROM THE BASIN FOREBAY AND OTHER AREAS TO RESTORE ORIGINAL DESIGN GRADES. DISTURBED AREAS SHALL BE RESTABILIZED AS REQUIRED AFTER REMOVAL OF SEDIMENT.
 - INLETS AND OUTLETS SHALL BE INSPECTED FOR SCOUR DAMAGE AND EROSION AND REPAIRED AS REQUIRED.
 - ANY EVIDENCE OF PIPING OR SEEPAGE AT THE TOE OF EMBANKMENTS OR AROUND INLET/OUTLET STRUCTURES SHALL BE INVESTIGATED BY A QUALIFIED PROFESSIONAL ENGINEER AND REPORTED TO THE TOWN. REQUIRED REPAIRS TO MAINTAIN THE PROPER FUNCTION OR REPAIR POTENTIAL STRUCTURAL DEFICIENCIES IN THE BASIN SHALL BE IMPLEMENTED WITHIN ONE MONTH OF DISCOVERY OF THE PROBLEM OR AT DISCRETION OF THE RESPONSIBLE PROFESSIONAL ENGINEER PERFORMING THE INVESTIGATION OR DESIGNING SUCH REPAIRS. THE ENGINEER SHALL CERTIFY THAT ALL REPAIRS ARE PERFORMED TO HIS/HER SATISFACTION AND SHALL PROVIDE SUCH CERTIFICATION TO THE TOWN.

STORMWATER SYSTEM OPERATION AND MAINTENANCE NOTES:

- PROVIDE ANNUAL STREET SWEEPING, PREFERABLY AFTER FINAL SNOW MELT TO ALLEVIATE SEDIMENT BUILDUP IN CATCH BASIN SUMPS AND TO INSURE EFFICIENT TSS REMOVAL FROM STORMWATER.
- REMOVE SEDIMENT FROM CATCH BASIN SUMPS WHEN SEDIMENT REACHES HALF THE DEPTH OF THE SUMP.
- INSPECT CATCH BASINS FOR TRASH AND DEBRIS BI-ANNUALLY. REMOVE ACCUMULATED SEDIMENT AND DEBRIS FROM PIPE INLETS AND OUTLETS TO PREVENT CLOGGING.
- REMOVE ACCUMULATED TRASH AND LEAVES FROM CATCH BASIN GRATES TO INSURE ADEQUATE GRATE INFLOW CAPACITIES.

APPROVED BY THE LEDYARD PLANNING AND ZONING COMMISSION AS TO THE COMPLIANCE WITH THE REGULATIONS GOVERNING THE SUBDIVISION OF LAND. ALL IMPROVEMENTS SHALL BE COMPLETED BY _____ DATE _____	
CHAIRMAN OR SECRETARY	DATE
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION ON _____ DATE _____	
LOT NUMBERS ASSIGNED BY THE ASSESSOR	
ASSESSOR	DATE
IWVC	APPLICATION#
	APPROVED.
NO PERMIT NECESSARY. (NOT WITHIN A REGULATED AREA)	
NOT APPLICABLE AT THIS TIME. (WITHIN A REGULATED AREA; NO REGULATED ACTIVITY PROPOSED AT THIS TIME.)	
WETLANDS OFFICER	DATE
APPROVED BY THE DIRECTOR OF PUBLIC WORKS OR THE TOWN ENGINEER FOR PUBLIC WAY LAYOUT.	
PUBLIC WORKS DIRECTOR/TOWN ENGINEER	DATE
EROSION AND SEDIMENT CONTROL PLAN CERTIFIED BY VOTE OF THE LEDYARD PLANNING AND ZONING COMMISSION	
CHAIRMAN OR SECRETARY OF THE LEDYARD PLANNING AND ZONING COMMISSION	DATE
APPROVED BY THE ZONING ENFORCEMENT OFFICER OF THE LEDYARD PLANNING COMMISSION	
ZONING ENFORCEMENT OFFICER	DATE



PLAN SHOWING
EROSION AND SEDIMENT CONTROL
NARRATIVE AND DETAILS
RESUBDIVISION
PROPERTY OF
AVERY BROOK HOMES LLC
94, 96, 98 AND 100
STODDARDS WHARF ROAD
A.K.A.
CONNECTICUT ROUTE 214
LEDYARD, CONNECTICUT

JULY 2022
REVISED: OCTOBER 31, 2022