PROPOSED HOUSING DEVELOPMENT

COLONEL LEDYARD HIGHWAY (RT 117) LEDYARD, CONNECTICUT

PREPARED FOR: ACRONOM MASONRY, INC

LEGEND

O IRON PIN FOUND

□ CHD PNT CHD MONUMENT POINT

I SIGN

ILIGHT POLE

Ø UTILITY POLE

O WG WATER GATE

O GG GAS GATE

THE HYDRANT

□ CB CATCH BASIN

O MH MANHOLE

---100--- EXISTING CONTOURS

INLAND WETLANDS FLAG

STONE WALL

BEFORE YOU DIG


AT LEAST TWO FULL BUSINESS DAYS BEFORE DIGGING OR DISTURBING EARTH DIAL 811 OR 1-800-922-4455

APPROVED BY THE LEDYARD

PLANNING & ZONING COMMISSION

DATE

CHAIRMAN



PREPARED BY:

	REVISIONS	
DATE	DESCRIPTION	
2/07/2024	PER STAFF COMMENTS	Killingly Engineering Associates
		Civil Engineering & Surveying
		114 Westcott Road P.O. Box 421 Killingly, Connecticut 06241 (860) 779-7299 www.killinglyengineering.com

OCTOBER 2024

INDEX TO DRAWINGS

TITLE	SHEET No.
COVER SHEET	1 OF 3
EXISTING CONDITIONS & DEMOLITION PLAN	2 OF 3
SITE DEVELOPMENT PLAN	3 OF 3

ARCHITECTURAL PLANS


FLOOR PLAN	A-1
BUILDING ELEVATIONS	A-2

CONSTRUCTION NOTES


- All Materials and methods of construction shall conform to "State of Connecticut, Department of Transportation, Standard Specifications for Roads, Bridges and Incidental Construction, Form 817", and supplements thereto.
- 2. In the event that ground water or evidence thereof is encountered, sufficient dewatering equipment, shall be installed and maintained to accommodate
- All existing site features not scheduled to remain shall be removed and disposed of in a proper manner, by the contractor.
- All reinforced concrete storm drainage pipes shall have gasketed rubber joints.
- All disturbed areas not scheduled for pavement, walks, etc. shall be permanently established as turf.
- 6. The location of existing utilities is shown for informational purposes only. It is the responsibility of the contractor to verify the location and elevation of all utilities. Contact "CALL BEFORE YOU DIG" at 1-800-922-4455, and obtain all applicable permits, prior to any excavation around utilities.


RECEIVED

Land Use Department



SHEET 1 OF 3 JOB NO: 23038





SILT FENCE @ TOE OF SLOPE APPLICATION

EROSION AND SEDIMENT CONTROL NARRATIVE:

PRINCIPLES OF EROSION AND SEDIMENT CONTROL

The primary function of erosion and sediment controls is to absorb erosional energies and reduce runoff velocities that force the detachment and transport of soil and/or encourage the deposition of eroded soil particles before they reach any sensitive area.

KEEP LAND DISTURBANCE TO A MINIMUM

The more land that is in vegetative cover, the more surface water will infiltrate into the soil, thus minimizing stormwater runoff and potential erosion. Keeping land disturbance to a minimum not only involves minimizing the extent of exposure at any one time, but also the duration of exposure. Phasing, sequencing and construction scheduling are interrelated. Phasing divides a large project into distinct sections where construction work over a specific area occurs over distinct periods of time and each phase is not dependent upon a subsequent phase in order to be functional. A sequence is the order in which construction activities are to occur during any particular phase. A sequence should be developed on the premise of "first things first" and "last things last" with proper attention given to the inclusion of adequate erosion and sediment control measures. A construction schedule is a sequence with time lines applied to it and should address the potential overlap of actions in a sequence which may be in conflict with each other.

- Limit areas of clearing and grading. Protect natural vegetation from construction equipment with fencing, tree armoring, and retaining walls or tree
- Route traffic patterns within the site to avoid existing or newly planted vegetation.
- Phase construction so that areas which are actively being developed at any one time are minimized and only that area under construction is exposed. Clear only those areas essential for construction.
- Sequence the construction of storm drainage systems so that they are operational as soon as possible during construction. Ensure all outlets are stable before outletting storm drainage flow into them.
- Schedule construction so that final grading and stabilization is completed as soon as possible.

SLOW THE FLOW

Detachment and transport of eroded soil must be kept to a minimum by absorbing and reducing the erosive energy of water. The erosive energy of water increases as the volume and velocity of runoff increases. The volume and velocity of runoff increases during development as a result of reduced infiltration rates caused by the removal of existing vegetation, removal of topsoil, compaction of soil and the construction of impositive purfaces. and the construction of impervious surfaces.

- Use diversions, stone dikes, silt fences and similar measures to break flow lines and dissipate storm water energy.
- Avoid diverting one drainage system into another without calculating the potential for downstream flooding or erosion.


KEEP CLEAN RUNOFF SEPARATED

Clean runoff should be kept separated from sediment laden water and should not be directed over disturbed areas without additional controls. Additionally, prevent the mixing of clean off—site generated runoff with sediment laden runoff generated on—site until after adequate filtration of on—site waters has occurred.


- Segregate construction waters from clean water.
- Divert site runoff to keep it isolated from wetlands, watercourses and drainage ways that flow through or near the development until the sediment in that runoff is trapped or detained.

NORMAND E. THIBEAULT, JR., P.E.

LIC #PEN 0022834



SILT FENCE



HAYBALE BARRIER NOT TO SCALE

02/07/2025	PER STAFF REVIEW
DATE	DESCRIPTION

SITE DEVELOPMENT PLAN **EXISTING CONDITIONS & DEMOLITION PLAN**

PREPARED FOR

ACRONOM MASONRY, INC

COLONEL LEDYARD HIGHWAY LEDYARD, CONNECTICUT





DATE

Killingly Engineering Associates Civil Engineering & Surveying

> 114 Westcott Road P.O. Box 421 Killingly, Connecticut 06241 (860) 779-7299 www.killinglyengineering.com

DATE: 10/15/2024 DRAWN: RGS SCALE: 1" = 20**DESIGN: NET** SHEET: 2 OF 3 CHK BY: ---DWG. No: CLIENT FILE JOB No: 23038





100 RIVERVIEW CENTER 292 MAIN STREET MIDDLETOWN, CT PHONE: (860) 346-1809 EMAIL: hra@hra.bz PROJECT:

PROPOSED APARTMENTS 740 COLONEL LEDYARD HWY LEDYARD, CT 06339

TITLE:

PROPOSED FLOOR PLAN

PRELIMINARY SET

DATES ISSUED:

COM. # 2024-39

SCALE:

SHEET:

1/8" = 1-0"

